

**Unity Place Apartments
Traffic Impact Analysis**

Shepherdsville Road, just south of
Robbs Lane / Applegate Lane
Louisville, Kentucky



Prepared for:
Barrister Commercial Group
3810 Springhurst Blvd
Louisville, KY 40241

Prepared by:
Stantec Consulting Services Inc.
801 Jones Franklin Road
Suite 300
Raleigh, NC 27606

RECEIVED
JUL 23 2018
**PLANNING &
DESIGN SERVICES**

July 13, 2018

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Table of Contents

1.0 INTRODUCTION 1
2.0 EXISTING CONDITIONS 2
3.0 FUTURE CONDITIONS 4
4.0 TRAFFIC ANALYSIS 12
4.1 IMPROVEMENTS 12
5.0 CONCLUSIONS..... 16

LIST OF TABLES

Table 1: Peak Hour Summary for Study Area Intersections 4
Table 2: Unity Place Apartments Trip Generation Table..... 7
Table 3: LOS and Delay Summary 13
Table 4: Volume to Capacity Ratio Summary 14

LIST OF FIGURES


Figure 1: Proposed Site Location 1
Figure 2: Existing Lane Configurations and Traffic Control..... 3
Figure 3: 2018 AM and PM Peak Hour Traffic Volumes 5
Figure 4: 2020 AM and PM Peak Hour Traffic Volumes 6
Figure 5: Site Plan 8
Figure 6: Site Trip Distribution 9
Figure 7: Peak Hour Site Trips..... 10
Figure 8: 2020 Build Out Traffic Volumes 11
Figure 9: 2020 Build Lane Configurations and Traffic Control 15

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Introduction
July 13, 2018

1.0 INTRODUCTION

Figure 1: Proposed Site Location



Barrister Commercial Group is proposing to construct 264 apartments on a 19.66 acre site located on the west side of Shepherdsville Road just south of the Robbs Lane / Applegate Lane intersection (see Figure 1). Construction for this development, referred to as Unity Place Apartments, is planned to be complete by the end of 2019. The current zoning for this property, which is currently vacant, is R-4 and C-1 while the proposed zoning is R-6 and C-1.

Stantec Consulting Services, Inc. prepared this report to present trip generation, trip distribution, and traffic analyses in order to identify the impacts the development will have on the adjacent transportation system. Study area intersections include Shepherdsville Road / Robbs Lane & Applegate Lane, Shepherdsville Road / Famous Way, Shepherdsville Road / Miles Lane, and two site access points on Shepherdsville Road. This report examines 2018 Existing conditions, 2020 No-Build conditions, and 2020 Build Out conditions for the AM and PM peak hours.

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Existing Conditions
July 13, 2018

2.0 EXISTING CONDITIONS

Shepherdsville Road runs north-south in southern Jefferson County connecting residential areas in the south to commercial, industrial and residential areas to the north. The posted speed limit on Shepherdsville Road is 35 miles per hour (mph). Kentucky Transportation Cabinet traffic station counts reported the following vpd along study area roads:

- Shepherdsville Road (north of Miles Lane) - 11,519 vpd in 2016
- Robb's Lane - 5,820 vpd in 2015
- Applegate Lane – 4,986 vpd in 2014
- Famous Way – 3,200 vpd in 2017
- Miles Lane – 3,031 vpd in 2017

City of Louisville public works department stated via email the daily traffic for Famous Way was 3,200 vehicles per day (vpd) in 2017. Within the study area, land uses around Shepherdsville Road are primarily low-density residential. Transit Authority of River City (TARC) bus service for the Breckenridge – Shepherdsville corridor is provided; although there are not transit stops within the study area.


According to the Kentucky Transportation Cabinet Functional Classification Interactive Map, Shepherdsville Road is a minor arterial whereas Robbs Lane / Applegate Lane and Miles Lane are listed as major collectors. Famous Way is shown as a local road.

Figure 2 illustrates the existing lane configurations and traffic control.

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Existing Conditions
July 13, 2018

Figure 2: Existing Lane Configurations and Traffic Control



UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Future Conditions
July 13, 2018

AM (7 – 9 AM) and PM (4 – 6 PM) peak hour traffic counts were collected at the intersections of Shepherdsville Road at Robbs / Applegate Lane and Shepherdsville Road at Miles Lane on May 18 & 19, 2016 (See Appendix). Traffic counts were performed at the intersection of Shepherdsville Road at Famous Way on June 20, 2018. Due to the distance and number of access locations between the study area intersections, they experienced slightly different PM peak hours. Table 1 summarizes the study area intersections and the actual AM and PM peak hour for each intersection.

Table 1: Peak Hour Summary for Study Area Intersections

Unity Place Apartments Peak Hour Summary for Study Area Intersections				
Intersection	Traffic Control	Data Collection Date	AM Peak Hour	PM Peak Hour
Shepherdsville Road / Robbs Ln & Applegate Ln	Signalized	May 18-19, 2016	7:00 – 8:00 AM	4:45 – 5:45 PM
Shepherdsville Road / Famous Way	Stop-Control	June 20, 2018	7:15 – 8:15 AM	4:45 – 5:45 PM
Shepherdsville Road / Miles Lane	Stop-Control	May 18-19, 2016	7:00 – 8:00 AM	4:30 – 5:30 PM

To estimate 2018 peak hour traffic volumes, data collected in 2016 was grown by 2.5% per year. Figure 3 summarizes the 2018 AM and PM peak hour traffic volumes. The traffic volumes may be overestimated due to an aggressive growth rate being assumed. To account for seasonal variation in traffic volumes, the data collected at the intersection of Shepherdsville Road at Famous Way was increased by a factor of 1.14. This factor was obtained from Table D3 contained in the Traffic Forecasting Report – 2008 produced by Kentucky Transportation Center at the University of Kentucky in cooperation with the Kentucky Transportation Cabinet.


3.0 FUTURE CONDITIONS

Construction of the Unity Place Apartments is expected to be complete by the end of 2019, therefore 2020 was used as the build out analysis year. To estimate 2020 No Build traffic volumes, the 2018 traffic volumes were grown by 2.5% per year. It should be noted that this is higher than observed traffic growth in the area; providing a conservative estimate of future traffic. Figure 4 illustrates the estimated 2020 No Build traffic volumes for the study area intersections.

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Future Conditions
 July 13, 2018


Figure 3: 2018 AM and PM Estimated Peak Hour Traffic Volumes



UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Future Conditions
July 13, 2018

Figure 4: 2020 No Build AM and PM Peak Hour Traffic Volumes



UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Future Conditions
July 13, 2018

The proposed development is planned to consist of 264 apartment units. Table 2 summarizes the expected trip generation according to the 10th Edition of the ITE Trip Generation Manual when using the peak hour of the adjacent street and the regression equations provided for daily, AM peak hour, and PM peak hour trip calculations.

Table 2: Unity Place Apartments Trip Generation Table

Unity Place Apartments Trip Generation							
Land Use (code)	Daily	AM			PM		
		TOTAL	IN	OUT	TOTAL	IN	OUT
264 Apartments (221)	1437	89	23	66	113	69	44

The daycare facility included on the site plan is the subject of a separate conditional use permit and is planned for future years; accordingly, this study focuses solely on the traffic impacts related to the proposed apartments.

The site plan for the proposed development shows a five-foot-wide sidewalk being constructed along the site's frontage of Shepherdsville Road. Additionally, a bike rack is shown to be installed on the south side of the complex's clubhouse. The site plan is shown on Figure 5.


To accurately determine the effect of the proposed development on the surrounding roadway network, an estimate of the expected distribution of traffic entering and exiting the site is needed. Generally, it is estimated that 55% of the traffic will travel to/from the north and 45% will travel to/from the south. Figure 6 shows the distributions described above as well as the turning movement percentages at each intersection. These percentages were developed using a combination of existing traffic volume counts in combination with an evaluation of surrounding land uses.

Figure 7 illustrates the traffic volumes expected to be generated by the proposed development and Figure 8 shows the 2020 Build Out traffic, which is a summary of the 2020 No Build traffic with the additional site traffic.

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Future Conditions
July 13, 2018


Figure 5: Site Plan



UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Future Conditions
July 13, 2018


Figure 6: Site Trip Distribution



UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Future Conditions
July 13, 2018


Figure 7: Peak Hour Site Trips



UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Future Conditions
July 13, 2018

Figure 8: 2020 Build Out Traffic Volumes



UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Traffic Analysis
July 13, 2018

4.0 TRAFFIC ANALYSIS

Capacity analyses were performed for the roadway network in the project study area. The traffic analysis program HCS Version 7 (Streets and TWSC) was used to analyze all intersections according to methods put forth by the Transportation Research Board's **Highway Capacity Manual**. Level-of-service (LOS) is a term used to describe different traffic conditions and is defined as a "qualitative measure describing operational conditions within a traffic stream, and their perception by motorists/ or passengers." LOS varies from Level A, representing free flow, to Level F where traffic breakdown conditions are evident.

At an unsignalized intersection, the primary traffic on the main roadway is virtually uninterrupted. Therefore, the overall delay for the intersection is usually less than what is calculated for the minor street movements. HCS 7 does not calculate an overall delay for unsignalized intersections; therefore, only the delay for the intersection's minor street(s) are reported in the summary tables of this report. With the current method of reporting LOS for unsignalized intersections, it is not uncommon for some of the minor street movements to be operating at a LOS F during peak hour conditions.

Capacity Analyses were performed for the following intersections defined within the study area for 2018 Existing, 2020 No-Build, 2020 Build Out conditions.

- Shepherdsville Road / Robbs Lane & Applegate Lane
- Shepherdsville Road / Famous Way
- Shepherdsville Road / Miles Lane

Famous Way is a local road approximately 0.75 miles in length. It provides access to single family homes. As the proposed development is envisioned to consist of apartments, predominantly residential areas are not anticipated to act as trip attractors for traffic traveling to/from the proposed development. Therefore, traffic generated by the proposed development is envisioned to be placed on thru movements on Shepherdsville Road and not on Famous Way.

The following intersections were also studied for the 2020 Build Out scenario:

- Shepherdsville Road / Access A
- Shepherdsville Road / Access B

Table 3 and Table 4 summarize the results from the capacity analyses. The recommended lane configuration and traffic control is shown on Figure 9.

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Traffic Analysis
July 13, 2018

Table 3: LOS and Delay Summary

LOS (Delay) Intersection		2018		2020			
		Existing		No-Build		Build	
		AM	PM	AM	PM	AM	PM
Shepherdsville Road at Robbs Lane / Applegate Lane (signalized)	Overall	D (39.4)	E (61.7)	D (40.9)	E (68.4)	D (42.1)	E (71.9)
	EB App.	D (39.6)	F (120.8)	D (39.8)	F (141.4)	D (39.9)	F (148.1)
	EB Left	E (55.4)	D (50.8)	E (56.9)	D (51.8)	E (56.9)	D (51.8)
	EB Thru/Right	D (38.7)	F (121.3)	D (38.9)	F (142.1)	D (39.1)	F (148.8)
	WB App.	D (50.1)	E (61.0)	D (51.6)	E (63.1)	D (51.6)	E (71.7)
	WB Left	D (42.9)	F (152.5)	D (43.4)	F (162.4)	D (43.7)	F (203.1)
	WB Thru/Right	D (51.4)	D (46.8)	D (53.1)	D (47.7)	D (53.1)	D (47.7)
	NB App.	D (38.7)	D (36.2)	D (40.8)	D (37.8)	D (43.5)	D (39.3)
	NB Left	B (15.2)	C (20.7)	B (15.4)	C (21.9)	B (15.6)	C (23.1)
	NB Thru/Right	D (41.0)	D (38.3)	D (43.3)	D (40.0)	D (46.4)	D (41.4)
	SB App.	C (28.5)	D (36.9)	C (29.0)	D (38.9)	C (29.4)	D (41.1)
	SB Left	B (19.8)	C (21.5)	C (20.8)	C (22.8)	C (22.0)	C (23.7)
SB Thru/Right	C (29.4)	D (40.4)	C (29.9)	D (42.7)	C (30.1)	D (44.9)	
Shepherdsville Road at Miles Lane*	EB App.	C (24.3)	F (64.4)	D (27.8)	F (92.4)	D (30.4)	F (126.7)
	NB Left	A (1.3)	A (1.3)	A (1.4)	A (1.4)	A (8.5)	A (9.9)
Shepherdsville Road at Famous Way*	EB App.	C (15.4)	E (45.6)	C (16.1)	F (59.6)	C (16.9)	F (69.4)
	NB Left	A (0.9)	A (1.3)	A (0.9)	A (1.4)	A (8.0)	B (10.1)
Shepherdsville Road at Access A*	EB	N/A	N/A	N/A	N/A	C (18.1)	D (26.4)
	NB Left	N/A	N/A	N/A	N/A	A (8.2)	A (9.5)
Shepherdsville Road at Access B*	EB	N/A	N/A	N/A	N/A	C (18.1)	D (26.6)
	NB Left	N/A	N/A	N/A	N/A	A (8.2)	A (9.5)

Legend:

X (X) LOS (Delay)

N/A Not Applicable for this Scenario

*Overall LOS not reported for unsignalized intersections

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Traffic Analysis
July 13, 2018

Table 4: Volume to Capacity Ratio Summary


Volume to Capacity Ratio Intersection		2018		2020			
		Existing		No-Build		Build	
		AM	PM	AM	PM	AM	PM
Shepherdsville Road at Robbs Lane / Applegate Lane	EB Left	0.026	0.020	0.028	0.021	0.028	0.021
	EB Thru/Right	0.170	1.103	0.181	1.159	0.189	1.176
	WB Left	0.166	0.827	0.177	0.870	0.184	1.023
	WB Thru/Right	0.664	0.540	0.700	0.569	0.700	0.569
	NB Left	0.092	0.168	0.099	0.185	0.113	0.202
	NB Thru/Right	0.755	0.697	0.794	0.734	0.836	0.761
	SB Left	0.077	0.303	0.086	0.332	0.091	0.344
	SB Thru/Right	0.394	0.746	0.415	0.786	0.426	0.819
Shepherdsville Road at Miles Lane	EB	0.40	0.83	0.45	0.95	0.48	1.06
	NB Left	0.05	0.05	0.05	0.05	0.05	0.06
Shepherdsville Road at Famous Way	EB	0.12	0.69	0.13	0.78	0.14	0.83
	NB Left	0.03	0.05	0.03	0.05	0.03	0.05
Shepherdsville Road at Access A	EB	N/A	N/A	N/A	N/A	0.10	0.12
	NB Left	N/A	N/A	N/A	N/A	0.01	0.02
Shepherdsville Road at Access B	EB	N/A	N/A	N/A	N/A	0.13	0.14
	NB Left	N/A	N/A	N/A	N/A	0.01	0.02

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Traffic Analysis
July 13, 2018

Figure 9: 2020 Build Lane Configurations and Traffic Control

Final7/13/18



UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Conclusions
July 13, 2018

5.0 CONCLUSIONS

According to the estimated trip generation for 264 apartments, the proposed site will generate 23 trips entering and 66 trips exiting in the AM peak hour and 69 trips entering and 44 trips exiting in the PM peak hour.

The additional site traffic is expected to increase the overall traffic volume at the signalized Shepherdsville Road / Robb Lane & Applegate Lane intersection by approximately 3.5% in the AM peak hour and 3% in the PM peak hour. Based on the results of the capacity analyses, the additional traffic will not increase overall delay by more than 3.5 seconds in either of the peak periods at the Shepherdsville Road / Robb Lane & Applegate Lane intersection. The additional traffic from the proposed development has a minimal impact. For the westbound left turn, the site is only expected to add 7 vehicles (an average of 1 vehicle every 8.5 minutes) to this movement.

As noted earlier, it is not uncommon for the stop-controlled minor streets in an unsignalized intersection to experience delays during peak periods, while the majority of the traffic flows through the intersection on the major street experiencing little or no delay. At the Shepherdsville Road intersections of Miles Lane and Famous Way, the eastbound approaches are anticipated to operate at LOS F with and without the proposed development.

Traffic exiting the proposed Access A and Access B is expected to operate at LOS C in the AM peak hour and LOS D in the PM peak hour. The left turns into the site are expected to operate at LOS A in both the AM and PM peak hours.

As part of the development, 5 foot sidewalks will be constructed along the property frontage on Shepherdsville Road and bike racks will be provided within the development.

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS



Appendix
July 13, 2018

APPENDIX

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Appendix
July 13, 2018

APPENDIX A: SITE PLAN



DETERMINATION CALCULATIONS

1. TOTAL AREA: 23.507 AC
 2. TOTAL AREA: 23.507 AC
 3. TOTAL AREA: 23.507 AC

THREE CANOPY CALCULATIONS

1. TOTAL AREA: 23.507 AC
 2. TOTAL AREA: 23.507 AC
 3. TOTAL AREA: 23.507 AC

LANDSCAPE DATA

1. TOTAL AREA: 23.507 AC
 2. TOTAL AREA: 23.507 AC
 3. TOTAL AREA: 23.507 AC

OPEN SPACE DATA (R-6)

1. TOTAL AREA: 23.507 AC
 2. TOTAL AREA: 23.507 AC
 3. TOTAL AREA: 23.507 AC

GENERAL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

TRANSPORTATION NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

EROSION CONTROL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

GENERAL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

TRANSPORTATION NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

EROSION CONTROL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

GENERAL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

TRANSPORTATION NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

EROSION CONTROL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

GENERAL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

TRANSPORTATION NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

EROSION CONTROL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

GENERAL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

TRANSPORTATION NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

EROSION CONTROL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

GENERAL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

TRANSPORTATION NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

EROSION CONTROL NOTES

1. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
2. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.
3. THE DEVELOPER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

Kentucky 811
 The law calls for utility locate in Kentucky. Call 811 before you dig.
 CALL 811 BEFORE YOU DIG

UTILITY NOTE:
 ALL UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE. INDIVIDUAL SERVICE LINES ARE NOT SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATION AND DEPTH OF ALL UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.

TYPICAL PARKING SPACE LAYOUT

OWNER: COMMERCIAL GROUP
OWNER'S REPRESENTATIVE: BARBARISTER
OWNER'S ADDRESS: 3810 SPRINGGURST BLVD, LOUISVILLE, KY 40241
OWNER'S PHONE: (502) 412-2800

PROJECT NO: 19-001
DATE: JANUARY 20, 2019
SCALE: 1"=20'-0"

REVISIONS:

NO.	DATE	DESCRIPTION
1	01/20/19	ISSUED FOR PERMIT
2	01/20/19	ISSUED FOR PERMIT
3	01/20/19	ISSUED FOR PERMIT

APPROVALS:

DESIGNER: [Signature]
CHECKED BY: BMS
DATE: 01/20/19

SCALE: 1"=20'-0"
GRAPHIC SCALE: 1"=20'-0"
NORTH: [Arrow pointing up]


CASE: 162061027 WMAF 11394

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Appendix
July 13, 2018


APPENDIX B: TRAFFIC COUNTS

Start Time	SHEPHERDSVILLE ROAD											SHEPHERDSVILLE ROAD											MILES LANE												
	From North					From East					From South					From West					From West					From West									
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total
07:00 AM	7	44	0	0	51	0	0	0	0	0	108	11	0	0	119	3	0	22	0	0	25	0	0	0	0	0	0	22	0	0	0	0	25	195	
07:15 AM	26	60	0	0	86	0	0	0	0	0	107	8	0	0	115	7	0	24	0	0	31	0	0	0	0	0	24	0	0	0	0	31	232		
07:30 AM	40	84	0	0	124	0	0	0	0	0	115	13	0	0	128	4	0	26	0	0	30	0	0	0	0	26	0	0	0	0	30	282			
07:45 AM	15	78	0	0	93	0	0	0	0	0	82	15	0	0	97	3	0	15	0	0	18	0	0	0	0	15	0	0	0	0	18	208			
Total	88	266	0	0	354	0	0	0	0	0	412	47	0	0	459	17	0	87	0	0	104	0	0	0	0	87	0	0	0	0	104	917			
08:00 AM	9	52	0	0	61	0	0	0	0	0	81	12	0	0	93	7	0	9	0	0	16	0	0	0	0	9	0	0	0	0	16	170			
08:15 AM	8	47	0	0	55	0	0	0	0	0	75	6	0	0	81	3	0	11	0	0	14	0	0	0	0	11	0	0	0	0	14	150			
08:30 AM	5	44	0	0	49	0	0	0	0	0	86	6	0	0	92	8	0	18	0	0	26	0	0	0	0	18	0	0	0	0	26	167			
08:45 AM	10	68	0	0	78	0	0	0	0	0	76	6	0	0	82	4	0	16	0	0	20	0	0	0	0	16	0	0	0	0	20	180			
Total	32	211	0	0	243	0	0	0	0	0	318	30	0	0	348	22	0	54	0	0	76	0	0	0	0	54	0	0	0	0	76	667			
Grand Total	120	477	0	0	597	0	0	0	0	0	730	77	0	0	807	39	0	141	0	0	180	0	0	0	0	141	0	0	0	0	180	1584			
Approch %	20.1	79.9	0	0	0	0	0	0	0	0	90.5	9.5	0	0	0	21.7	0	78.3	0	0	0	0	0	0	0	78.3	0	0	0	0	0	0	0		
Total %	7.6	30.1	0	0	37.7	0	0	0	0	0	46.1	4.9	0	0	50.9	2.5	0	8.9	0	0	11.4	0	0	0	0	8.9	0	0	0	0	11.4	0	0		
% Cars	116	463	0	0	579	0	0	0	0	0	711	77	0	0	788	39	0	136	0	0	175	0	0	0	0	136	0	0	0	0	175	1542			
% Trucks	96.7	97.1	0	0	97	0	0	0	0	0	97.4	100	0	0	97.6	100	0	96.5	0	0	97.2	0	0	0	0	96.5	0	0	0	0	97.2	97.3			
% Buses	0	5	0	0	5	0	0	0	0	0	8	0	0	0	8	0	0	1	0	0	1	0	0	0	0	1	0	0	0	0	1	14			
% Trucks	0	1	0	0	0.8	0	0	0	0	0	1.1	0	0	0	1	0	0	0.7	0	0	0.6	0	0	0	0	0.7	0	0	0	0	0.6	0.9			
% Buses	4	9	0	0	13	0	0	0	0	0	11	0	0	0	11	0	0	4	0	0	4	0	0	0	0	4	0	0	0	4	28				
% Buses	3.3	1.9	0	0	2.2	0	0	0	0	0	1.5	0	0	0	1.4	0	0	2.8	0	0	2.2	0	0	0	0	2.8	0	0	0	0	2.2	1.8			



Start Time	SHEPHERDVILLE ROAD							SHEPHERDVILLE ROAD							MILES LANE										
	From North				From East				From South				From West				From West								
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total				
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																									
Peak Hour for Entire Intersection Begins at 07:00 AM																									
07:00 AM	7	44	0	0	51	0	0	0	0	0	0	108	11	0	119	0	0	22	0	25	0	0	22	0	195
07:15 AM	26	60	0	0	86	0	0	0	0	0	0	107	8	0	115	0	0	24	0	31	0	0	24	0	232
07:30 AM	40	84	0	0	124	0	0	0	0	0	0	115	13	0	128	0	0	26	0	30	0	0	26	0	282
07:45 AM	15	78	0	0	93	0	0	0	0	0	0	82	15	0	97	0	0	15	0	18	0	0	15	0	208
Total Volume	88	266	0	0	354	0	0	0	0	0	0	412	47	0	459	0	0	87	0	104	0	0	87	0	917
% App. Total	24.9	75.1	0	0	714	0	0	0	0	0	0	89.8	10.2	0	100.0	0	0	83.7	0	16.3	0	0	83.7	0	839
PHF	.550	.792	.000	.000	.714	.000	.000	.000	.000	.000	.000	.896	.783	.000	.896	.607	.000	.837	.000	.839	.000	.000	.837	.000	.813

Start Time	SHEPHERDSVILLE ROAD												SHEPHERDSVILLE ROAD												MILES LANE																				
	From North						From East						From South						From West						From West																				
	Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total																
04:00 PM	30	103	0	0	133	0	0	0	0	0	0	0	104	8	0	112	0	0	0	0	0	0	0	104	8	0	112	0	0	0	0	0	0	10	0	20	0	30	0	10	0	20	0	30	0
04:15 PM	33	124	0	0	157	0	0	0	0	0	0	0	100	8	0	108	0	0	0	0	0	0	0	100	8	0	108	0	0	0	0	0	0	9	0	16	0	25	0	9	0	16	0	25	0
04:30 PM	49	112	0	0	161	0	0	0	0	0	0	0	120	9	0	129	0	0	0	0	0	0	0	120	9	0	129	0	0	0	0	0	0	15	0	18	0	33	0	15	0	18	0	33	0
04:45 PM	41	129	0	0	170	0	0	0	0	0	0	0	117	4	0	121	0	0	0	0	0	0	0	117	4	0	121	0	0	0	0	0	0	22	0	20	0	42	0	22	0	20	0	42	0
Total	153	468	0	0	621	0	0	0	0	0	0	0	441	29	0	470	0	0	0	0	0	0	0	441	29	0	470	0	0	0	0	0	0	56	0	74	0	130	0	56	0	74	0	130	0
05:00 PM	44	125	0	1	170	0	0	0	0	0	0	0	99	12	0	111	0	0	0	0	0	0	0	99	12	0	111	0	0	0	0	0	0	21	0	24	0	45	0	21	0	24	0	45	0
05:15 PM	43	140	0	0	183	0	0	0	0	0	0	0	123	10	0	133	0	0	0	0	0	0	0	123	10	0	133	0	0	0	0	0	0	40	0	20	0	60	0	40	0	20	0	60	0
05:30 PM	28	122	0	0	150	0	0	0	0	0	0	0	108	21	0	129	0	0	0	0	0	0	0	108	21	0	129	0	0	0	0	0	0	20	0	22	0	42	0	20	0	22	0	42	0
05:45 PM	34	137	0	0	171	0	0	0	0	0	0	0	114	10	0	124	0	0	0	0	0	0	0	114	10	0	124	0	0	0	0	0	0	14	0	22	0	36	0	14	0	22	0	36	0
Total	149	524	0	1	674	0	0	0	0	0	0	0	444	53	0	497	0	0	0	0	0	0	0	444	53	0	497	0	0	0	0	0	0	95	0	88	0	183	0	95	0	88	0	183	0
Grand Total	302	992	0	1	1295	0	0	0	0	0	0	0	885	82	0	967	0	0	0	0	0	0	0	885	82	0	967	0	0	0	0	0	0	151	0	162	0	313	0	151	0	162	0	313	0
Approch %	23.3	76.6	0	0.1		0	0	0	0	0	0	0	91.5	8.5	0		0	0	0	0	0	0	0	91.5	8.5	0		0	0	0	0	0	0	48.2	0	51.8	0		0	48.2	0	51.8	0		0
Total %	11.7	38.5	0	0	50.3	0	0	0	0	0	0	0	34.4	3.2	0	37.6	0	0	0	0	0	0	0	34.4	3.2	0	37.6	0	0	0	0	0	0	5.9	0	6.3	0	12.2	0	5.9	0	6.3	0	12.2	0
% Cars	298	989	0	0	1287	0	0	0	0	0	0	0	883	82	0	965	0	0	0	0	0	0	0	883	82	0	965	0	0	0	0	0	0	151	0	162	0	313	0	151	0	162	0	313	0
% Trucks	98.7	99.7	0	0	99.4	0	0	0	0	0	0	0	99.8	100	0	99.8	0	0	0	0	0	0	0	99.8	100	0	99.8	0	0	0	0	0	0	100	0	100	0	100	0	100	0	100	0	100	0
% Buses	2	2	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
% Trucks	0.7	0.2	0	0	0.3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
% Buses	2	1	0	1	4	0	0	0	0	0	0	0	2	0	0	2	0	0	0	0	0	0	0	2	0	0	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
% Buses	0.7	0.1	0	100	0.3	0	0	0	0	0	0	0	0.2	0	0	0.2	0	0	0	0	0	0	0	0.2	0	0	0.2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0



Start Time	SHEPHERDVILLE ROAD From North						SHEPHERDVILLE ROAD From East						SHEPHERDVILLE ROAD From South						MILES LANE From West					
	Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total	
04:30 PM	49	112	0	0	161		0	0	0	0	0		0	120	9	0	129		0	15	18	0	33	
04:45 PM	41	129	0	0	170		0	0	0	0	0		0	117	4	0	121		0	22	20	0	42	
05:00 PM	44	125	0	1	170		0	0	0	0	0		0	99	12	0	111		0	21	24	0	45	
05:15 PM	43	140	0	0	183		0	0	0	0	0		0	123	10	0	133		0	40	20	0	60	
Total Volume	177	506	0	1	684		0	0	0	0	0		0	459	35	0	494		0	98	82	0	180	
% App. Total	25.9	74	0	0.1	934		0	0	0	0	0		0	92.9	7.1	0	99.4		0	54.4	45.6	0	750	
PHF	903	904	0	.250	934		0	0	0	0	0		0	933	729	.000	929		0	613	854	.000	750	

Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1
 Peak Hour for Entire Intersection Begins at 04:30 PM

Famous at KY2052 - TMC

Wed Jun 20, 2018

Full Length (7AM-9AM, 4PM-6PM)

All Classes (Lights and Motorcycles, Heavy)

All Movements

ID: 539449, Location: 38.129641, -85.661617, Site Code: Site 1 -

Wednesday

Provided by: Cummins Consulting Services,

PLLC

4661 Marlberry Place, Lexington, KY, 40509, US

Leg Direction	KY2052 - Shepherdsville Road Eastbound				KY2052 - Shepherdsville Road Westbound				Famous Way Southbound				
Time	L	T	U	App	T	R	U	App	L	R	U	App	Int
2018-06-20 7:00AM	3	90	0	93	38	2	0	40	7	3	0	10	143
7:15AM	5	115	0	120	46	2	0	48	9	5	0	14	182
7:30AM	9	127	0	136	54	4	0	58	6	3	0	9	203
7:45AM	10	96	0	106	49	5	0	54	4	5	0	9	169
Hourly Total	27	428	0	455	187	13	0	200	26	16	0	42	697
8:00AM	7	79	0	86	64	4	0	68	5	1	0	6	160
8:15AM	3	91	0	94	42	2	0	44	5	6	0	11	149
8:30AM	9	87	0	96	51	9	0	60	10	3	0	13	169
8:45AM	10	70	0	80	56	9	0	65	9	4	0	13	158
Hourly Total	29	327	0	356	213	24	0	237	29	14	0	43	636
4:00PM	10	99	0	109	126	17	0	143	12	15	0	27	279
4:15PM	10	97	0	107	148	9	0	157	11	23	0	34	298
4:30PM	6	98	0	104	130	13	0	143	11	13	0	24	271
4:45PM	5	89	0	94	157	12	0	169	7	29	0	36	299
Hourly Total	31	383	0	414	561	51	0	612	41	80	0	121	1147
5:00PM	9	102	0	111	177	7	0	184	8	20	0	28	323
5:15PM	5	112	0	117	138	18	0	156	13	34	0	47	320
5:30PM	11	114	0	125	149	5	0	154	13	15	0	28	307
5:45PM	7	80	0	87	115	15	0	130	22	18	0	40	257
Hourly Total	32	408	0	440	579	45	0	624	56	87	0	143	1207
Total	119	1546	0	1665	1540	133	0	1673	152	197	0	349	3687
% Approach	7.1%	92.9%	0%	-	92.1%	7.9%	0%	-	43.6%	56.4%	0%	-	-
% Total	3.2%	41.9%	0%	45.2%	41.8%	3.6%	0%	45.4%	4.1%	5.3%	0%	9.5%	-
Lights and Motorcycles	119	1524	0	1643	1513	132	0	1645	148	195	0	343	3631
% Lights and Motorcycles	100%	98.6%	0%	98.7%	98.2%	99.2%	0%	98.3%	97.4%	99.0%	0%	98.3%	98.5%
Heavy	0	22	0	22	27	1	0	28	4	2	0	6	56
% Heavy	0%	1.4%	0%	1.3%	1.8%	0.8%	0%	1.7%	2.6%	1.0%	0%	1.7%	1.5%

*L: Left, R: Right, T: Thru, U: U-Turn

Famous at KY2052 - TMC

Wed Jun 20, 2018

AM Peak (7:15AM - 8:15AM)

All Classes (Lights and Motorcycles, Heavy)

All Movements

ID: 539449, Location: 38.129641, -85.661617, Site Code: Site 1 -

Wednesday

Provided by: Cummins Consulting Services,

PLLC

4661 Marlberry Place, Lexington, KY, 40509, US

Leg Direction	KY2052 - Shepherdsville Road Eastbound				KY2052 - Shepherdsville Road Westbound				Famous Way Southbound				
Time	L	T	U	App	T	R	U	App	L	R	U	App	Int
2018-06-20 7:15AM	5	115	0	120	46	2	0	48	9	5	0	14	182
7:30AM	9	127	0	136	54	4	0	58	6	3	0	9	203
7:45AM	10	96	0	106	49	5	0	54	4	5	0	9	169
8:00AM	7	79	0	86	64	4	0	68	5	1	0	6	160
Total	31	417	0	448	213	15	0	228	24	14	0	38	714
% Approach	6.9%	93.1%	0%	-	93.4%	6.6%	0%	-	63.2%	36.8%	0%	-	-
% Total	4.3%	58.4%	0%	62.7%	29.8%	2.1%	0%	31.9%	3.4%	2.0%	0%	5.3%	-
PHF	0.775	0.821	-	0.824	0.832	0.750	-	0.838	0.667	0.700	-	0.679	0.879
Lights and Motorcycles	31	414	0	445	206	15	0	221	23	14	0	37	703
% Lights and Motorcycles	100%	99.3%	0%	99.3%	96.7%	100%	0%	96.9%	95.8%	100%	0%	97.4%	98.5%
Heavy	0	3	0	3	7	0	0	7	1	0	0	1	11
% Heavy	0%	0.7%	0%	0.7%	3.3%	0%	0%	3.1%	4.2%	0%	0%	2.6%	1.5%

*L: Left, R: Right, T: Thru, U: U-Turn

Famous at KY2052 - TMC

Wed Jun 20, 2018

PM Peak (4:45PM - 5:45PM) - Overall Peak Hour

All Classes (Lights and Motorcycles, Heavy)

All Movements

ID: 539449, Location: 38.129641, -85.661617, Site Code: Site 1 -

Wednesday

Provided by: Cummins Consulting Services,

PLLC


4661 Marlberry Place, Lexington, KY, 40509, US

Leg Direction	KY2052 - Shepherdsville Road Eastbound				KY2052 - Shepherdsville Road Westbound				Famous Way Southbound				Int
	L	T	U	App	T	R	U	App	L	R	U	App	
2018-06-20 4:45PM	5	89	0	94	157	12	0	169	7	29	0	36	299
5:00PM	9	102	0	111	177	7	0	184	8	20	0	28	323
5:15PM	5	112	0	117	138	18	0	156	13	34	0	47	320
5:30PM	11	114	0	125	149	5	0	154	13	15	0	28	307
Total	30	417	0	447	621	42	0	663	41	98	0	139	1249
% Approach	6.7%	93.3%	0%	-	93.7%	6.3%	0%	-	29.5%	70.5%	0%	-	-
% Total	2.4%	33.4%	0%	35.8%	49.7%	3.4%	0%	53.1%	3.3%	7.8%	0%	11.1%	-
PHF	0.682	0.914	-	0.894	0.877	0.583	-	0.901	0.788	0.721	-	0.739	0.967
Lights and Motorcycles	30	413	0	443	615	42	0	657	40	96	0	136	1236
% Lights and Motorcycles	100%	99.0%	0%	99.1%	99.0%	100%	0%	99.1%	97.6%	98.0%	0%	97.8%	99.0%
Heavy	0	4	0	4	6	0	0	6	1	2	0	3	13
% Heavy	0%	1.0%	0%	0.9%	1.0%	0%	0%	0.9%	2.4%	2.0%	0%	2.2%	1.0%

*L: Left, R: Right, T: Thru, U: U-Turn


File Name : Shepherdsville Road @ Robbs Lane AM
 Site Code : 00000000
 Start Date : 5/19/2016
 Page No : 1

Start Time	Groups Printed- Cars - Buses - Trucks																				
	SHEPHERDSDVILLE ROAD				APPLGATE LANE				SHEPHERDSDVILLE ROAD				ROBBS LANE								
	From North		From East		From South		From West		From North		From East		From South		From West						
Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total	
07:00 AM	1	40	10	0	51	27	51	10	0	88	15	142	12	0	169	4	13	1	0	18	326
07:15 AM	2	82	10	0	94	22	38	15	0	75	13	123	10	0	146	9	7	0	0	16	331
07:30 AM	1	73	4	0	78	30	49	16	0	95	20	108	12	0	140	6	13	1	1	21	334
07:45 AM	3	66	4	0	73	23	44	12	0	79	5	79	15	0	99	9	12	2	0	23	274
Total	7	261	28	0	296	102	182	53	0	337	53	452	49	0	554	28	45	4	1	78	1265
08:00 AM	1	38	6	0	45	18	31	4	0	53	4	86	3	0	93	5	15	0	0	20	211
08:15 AM	0	29	11	0	40	17	33	7	0	57	10	76	15	0	101	3	14	2	0	19	217
08:30 AM	2	59	8	0	69	15	25	7	0	47	9	100	16	0	125	7	16	0	1	24	265
08:45 AM	1	66	8	0	75	18	35	3	0	56	7	74	11	0	92	6	5	0	0	11	234
Total	4	192	33	0	229	68	124	21	0	213	30	336	45	0	411	21	50	2	1	74	927
Grand Total	11	453	61	0	525	170	306	74	0	550	83	788	94	0	965	49	95	6	2	152	2192
Apprch %	2.1	86.3	11.6	0	30.9	8.6	81.7	9.7	0	32.2	62.5	3.9	1.3	0	44	2.2	4.3	0.3	0.1	6.9	
Total %	0.5	20.7	2.8	0	24	7.8	14	3.4	0	25.1	3.8	35.9	4.3	0	44	2.2	4.3	0.3	0.1	6.9	
% Cars	11	443	60	0	514	169	306	72	0	547	81	774	93	0	948	47	93	6	2	148	2157
% Buses	0	5	1	0	6	1	0	2	0	3	2	3	0	0	5	0	2	0	0	2	16
% Trucks	0	1.1	1.6	0	1.1	0.6	0	2.7	0	0.5	2.4	0.4	0	0	0.5	0	2.1	0	0	1.3	0.7
% Trucks	0	5	0	0	5	0	0	0	0	0	0	11	1	0	12	2	0	0	0	2	19
% Trucks	0	1.1	0	0	1	0	0	0	0	0	0	1.4	1.1	0	1.2	4.1	0	0	0	1.3	0.9



File Name : Shepherdsville Road @ Robbs Lane AM
 Site Code : 00000000
 Start Date : 5/19/2016
 Page No : 3

Start Time	SHEPHERDSVILLE ROAD From North				APPLEGATE LANE From East				SHEPHERDSVILLE ROAD From South				ROBBS LANE From West								
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:00 AM																					
07:00 AM	1	40	10	0	51	27	51	10	0	88	15	142	12	0	169	4	13	1	0	18	326
07:15 AM	2	82	10	0	94	22	38	15	0	75	13	123	10	0	146	9	7	0	0	16	331
07:30 AM	1	73	4	0	78	30	49	16	0	95	20	108	12	0	140	6	13	1	1	21	334
07:45 AM	3	66	4	0	73	23	44	12	0	79	5	79	15	0	99	9	12	2	0	23	274
Total Volume	7	261	28	0	296	102	182	53	0	337	53	452	49	0	554	28	45	4	1	78	1265
% App. Total	2.4	88.2	9.5	0	78.7	30.3	54	15.7	0	81.6	9.6	81.6	8.8	0	35.9	57.7	5.1	1.3	0	250	947
PHF	.583	.796	.700	.000	.887	.850	.892	.828	.000	.887	.663	.796	.817	.000	.820	.778	.865	.500	.250	.848	



File Name : Shepherdsville Road @ Robbs Lane PM
 Site Code : 00000000
 Start Date : 5/18/2016
 Page No : 3

Start Time	SHEPHERDSVILLE ROAD From North				APPLGATE LANE From East				SHEPHERDSVILLE ROAD From South				ROBBS LANE From West							
	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total				
04:45 PM	1	124	33	0	158	15	47	8	1	71	19	101	15	1	136	90	2	0	115	480
05:00 PM	4	104	14	0	122	16	36	13	0	65	17	77	17	0	111	104	0	0	120	418
05:15 PM	2	144	34	0	180	22	37	8	0	67	26	98	17	0	141	25	0	1	121	509
05:30 PM	2	127	36	0	165	16	45	7	0	68	26	96	12	0	134	29	2	0	133	500
Total Volume	9	499	117	0	625	69	165	36	1	271	88	372	61	1	522	93	4	1	489	1907
% App. Total	1.4	79.8	18.7	0	868	25.5	60.9	13.3	0.4	954	16.9	71.3	11.7	0.2	926	802	0.8	0.2	250	937
PHF	.563	.866	.813	.000	.868	.784	.878	.692	.250	.954	.846	.921	.897	.250	.926	.802	.500	.250	.919	.937

Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1
 Peak Hour for Entire Intersection Begins at 04:45 PM

Appendix
July 13, 2018

APPENDIX C: TRAFFIC VOLUME CALCULATIONS

Unity Place Apartments TIA: Traffic Volume Calculations

	Counted Volumes (2016)		Counted Volumes (2018)		Existing (2018)		Background (2020)		No Build (2020)		Site Trip Distribution		Site Trip Assignment		Build (2020)	
	AM	PM	AM	PM	AM	PM	AM	PM	AM	PM	Enter	Exit	AM	PM	AM	PM
	Site Trips															
Intersection 1 - Shepherdsville Road at Robbs Lane / Applegate Lane																
EBL	4	4			4	4	4	4	4	4			0	0	4	4
EBT	45	391			47	411	50	432	50	432			0	0	50	432
EBR	28	93			29	98	31	103	31	103	10%		3	7	34	110
WBL	53	36			56	38	59	40	59	40	10%		2	7	61	47
WBT	182	165			191	173	201	182	201	182			0	0	201	182
WBR	102	69			107	72	113	76	113	76			0	0	113	76
NBL	49	61			51	64	54	67	54	67		10%	7	5	61	70
NBT	452	372			475	391	499	411	499	411		35%	23	15	522	426
NBR	53	88			56	92	59	97	59	97		10%	6	4	65	101
SBL	28	117			29	123	31	129	31	129			0	0	31	129
SBT	261	499			274	524	288	551	288	551	35%		8	24	296	575
SBR	7	9			7	9	8	10	8	10			0	0	8	10

Intersection 2 - Shepherdsville Road at Miles Lane																
EBL	87	82			91	86	96	91	96	91	10%		2	7	98	98
EBR	17	98			18	103	19	108	19	108			0	0	19	108
NBL	47	35			49	37	52	39	52	39			0	0	52	39
NBT	412	459			433	482	455	507	455	507	35%		8	24	463	531
SBT	266	506			279	532	294	559	294	559		35%	23	15	317	574
SBR	88	177			92	186	97	195	97	195		10%	7	5	104	200

Intersection 3 - Shepherdsville Road at Site Access A																
EBL												25%	16	11	16	11
EBR												20%	13	9	13	9
NBL											20%		5	14	5	14
NBT	554	521			582	547	612	575	612	575		30%	20	13	632	588
SBT	342	628			359	660	378	693	378	693	30%		7	21	385	714
SBR											25%		6	17	6	17

Intersection 4 - Shepherdsville Road at Site Access B																
EBL												30%	20	13	20	13
EBR												25%	17	11	17	11
NBL											25%		5	17	5	17
NBT	554	521			582	547	612	575	612	575	20%		5	14	617	589
SBT	342	628			359	660	378	693	378	693		20%	13	9	391	702
SBR											30%		7	21	7	21

Intersection 6 - Shepherdsville Road at Famous Way																
EBL			24	41	27	47	28	49	28	49			0	0	28	49
EBR			14	98	16	112	17	118	17	118			0	0	17	118
NBL			31	30	35	34	37	36	37	36			0	0	37	36
NBT			417	417	475	475	499	499	499	499	45%		10	31	509	530
SBT			213	621	243	708	255	744	255	744		45%	30	20	285	764
SBR			15	42	17	48	18	50	18	50			0	0	18	50

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Appendix
July 13, 2018

APPENDIX D: HCS RESULTS


UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Appendix
July 13, 2018

APPENDIX D-1: 2018 EXISTING AM

HCS7 Signalized Intersection Results Summary

General Information				Intersection Information	
Agency	Stantec			Duration, h	0.25
Analyst	M. Peach	Analysis Date	Apr 19, 2018	Area Type	Other
Jurisdiction	Louisville, Kentucky	Time Period	AM Peak Hour	PHF	0.90
Urban Street	Shepherdsville Road	Analysis Year	2018	Analysis Period	1 > 7:00
Intersection	Robbs Lane / Applegate...	File Name	2018_AM_Ex_Signal_Intersection1.xus		
Project Description	2018 Existing AM Peak Hour				



Demand Information	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Approach Movement												
Demand (v), veh/h	4	47	29	56	191	107	51	475	56	29	274	7

Signal Information													
Cycle, s	141.0	Reference Phase	2										
Offset, s	0	Reference Point	End										
Uncoordinated	Yes	Simult. Gap E/W	On	Green	20.0	60.0	40.0	0.0	0.0	0.0			
		Yellow		5.0	5.0	5.0	0.0	0.0	0.0				
Force Mode	Fixed	Simult. Gap N/S	On	Red	2.0	2.0	2.0	0.0	0.0	0.0			

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		47.0		47.0	27.0	67.0	27.0	67.0
Change Period, (Y+R _c), s		7.0		7.0	7.0	7.0	7.0	7.0
Max Allow Headway (MAH), s		3.2		3.2	3.1	3.1	3.1	3.1
Queue Clearance Time (g _s), s		26.0		25.5	4.0	40.4	3.1	18.3
Green Extension Time (g _e), s		0.9		0.9	0.1	1.8	0.0	1.8
Phase Call Probability		1.00		1.00	1.00	1.00	1.00	1.00
Max Out Probability		0.00		0.00	0.00	0.00	0.00	0.00

Movement Group Results	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	4	84		62	331		57	590		32	312	
Adjusted Saturation Flow Rate (s), veh/h/ln	1049	1750		1313	1757		1781	1836		1781	1862	
Queue Service Time (g _s), s	0.5	5.1		5.3	23.5		2.0	38.4		1.1	16.3	
Cycle Queue Clearance Time (g _c), s	24.0	5.1		10.4	23.5		2.0	38.4		1.1	16.3	
Green Ratio (g/C)	0.28	0.28		0.28	0.28		0.57	0.43		0.57	0.43	
Capacity (c), veh/h	174	497		376	498		619	781		419	792	
Volume-to-Capacity Ratio (X)	0.026	0.170		0.166	0.664		0.092	0.755		0.077	0.394	
Back of Queue (Q), ft/ln (50 th percentile)	3.9	58.8		46.3	282.4		21.7	464.9		12.5	192.8	
Back of Queue (Q), veh/ln (50 th percentile)	0.2	2.3		1.8	11.1		0.9	18.3		0.5	7.6	
Queue Storage Ratio (RQ) (50 th percentile)	0.05	0.00		0.46	0.00		0.19	0.00		0.00	0.00	
Uniform Delay (d ₁), s/veh	55.2	38.0		41.9	44.6		14.9	34.3		19.5	28.0	
Incremental Delay (d ₂), s/veh	0.3	0.7		0.9	6.8		0.3	6.7		0.4	1.5	
Initial Queue Delay (d ₃), s/veh	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Control Delay (d), s/veh	55.4	38.7		42.9	51.4		15.2	41.0		19.8	29.4	
Level of Service (LOS)	E	D		D	D		B	D		B	C	
Approach Delay, s/veh / LOS	39.6		D	50.1		D	38.7		D	28.5		C
Intersection Delay, s/veh / LOS	39.4						D					

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.3	B	2.3	B	2.3	B	2.3	B
Bicycle LOS Score / LOS	0.6	A	1.1	A	1.6	B	1.1	A

HCS7 Two-Way Stop-Control Report


General Information

Analyst	M. Peach
Agency/Co.	Stantec
Date Performed	4/19/2018
Analysis Year	2018
Time Analyzed	Existing AM Peak Hour
Intersection Orientation	North-South
Project Description	Unity Place Apartments TIA

Site Information

Intersection	Shepherdsville / Famous
Jurisdiction	Louisville, Kentucky
East/West Street	Famous Way
North/South Street	Shepherdsville Road
Peak Hour Factor	0.90
Analysis Time Period (hrs)	0.25

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	0	0		0	0	0		0	1	0		0	1	0	
Configuration			LR							LT						TR	
Volume, V (veh/h)		27		16						35	475				243	17	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)																	
Critical Headway (sec)																	
Base Follow-Up Headway (sec)																	
Follow-Up Headway (sec)																	


Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			48									39					
Capacity, c (veh/h)			393									1272					
v/c Ratio			0.12									0.03					
95% Queue Length, Q ₉₅ (veh)			0.4									0.1					
Control Delay (s/veh)			15.4									7.9					
Level of Service, LOS			C									A					
Approach Delay (s/veh)		15.4										0.9					
Approach LOS		C															

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach	Intersection	Shepherdsville / Miles				
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky				
Date Performed	4/19/2018	East/West Street	Miles Lane				
Analysis Year	2018	North/South Street	Shepherdsville Road				
Time Analyzed	Existing AM Peak Hour	Peak Hour Factor	0.90				
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25				
Project Description	Unity Place Apartments TIA						

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	1	0		0	0	0		0	1	0		0	1	0	
Configuration			LR							LT						TR	
Volume, V (veh/h)		91		18						49	433				279	92	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)																
Critical Headway (sec)																
Base Follow-Up Headway (sec)																
Follow-Up Headway (sec)																

Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			121								54					
Capacity, c (veh/h)			305								1146					
v/c Ratio			0.40								0.05					
95% Queue Length, Q ₉₅ (veh)			1.8								0.1					
Control Delay (s/veh)			24.3								8.3					
Level of Service, LOS			C								A					
Approach Delay (s/veh)		24.3										1.3				
Approach LOS		C														


UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Appendix
July 13, 2018

APPENDIX D-2: 2018 EXISTING PM

HCS7 Signalized Intersection Results Summary

General Information					Intersection Information			
Agency	Stantec			Duration, h	0.25			
Analyst	M. Peach	Analysis Date	Apr 19, 2018		Area Type	Other		
Jurisdiction	Louisville, Kentucky	Time Period	PM Peak Hour		PHF	0.90		
Urban Street	Shepherdsville Road	Analysis Year	2018		Analysis Period	1 > 4:00		
Intersection	Robbs Lane / Applegate...	File Name	2018_PM_Ex_Signal_Intersection1.xus					
Project Description	2018 Existing PM Peak Hour							



Demand Information	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Approach Movement												
Demand (v), veh/h	4	411	98	38	173	72	64	391	92	123	524	9

Signal Information				Signal Phases						Signal Diagram			
Cycle, s	141.0	Reference Phase	2	Green	20.0	60.0	40.0	0.0	0.0	0.0	Green	Green	Green
Offset, s	0	Reference Point	End	Yellow	5.0	5.0	5.0	0.0	0.0	0.0	Yellow	Yellow	Yellow
Uncoordinated	Yes	Simult. Gap E/W	On	Red	2.0	2.0	2.0	0.0	0.0	0.0	Red	Red	Red
Force Mode	Fixed	Simult. Gap N/S	On										

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		47.0		47.0	27.0	67.0	27.0	67.0
Change Period, (Y+R c), s		7.0		7.0	7.0	7.0	7.0	7.0
Max Allow Headway (MAH), s		3.2		3.2	3.1	3.1	3.1	3.1
Queue Clearance Time (g s), s		42.0		42.0	4.5	36.2	7.1	39.7
Green Extension Time (g e), s		0.0		0.0	0.1	2.3	0.2	2.3
Phase Call Probability		1.00		1.00	1.00	1.00	1.00	1.00
Max Out Probability		1.00		1.00	0.00	0.00	0.00	0.01


Movement Group Results	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Approach Movement												
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	4	566		42	272		71	537		137	592	
Adjusted Saturation Flow Rate (s), veh/h/ln	1107	1808		845	1776		1781	1808		1781	1865	
Queue Service Time (g s), s	0.5	40.0		0.0	18.3		2.5	34.2		5.1	37.7	
Cycle Queue Clearance Time (g c), s	18.8	40.0		40.0	18.3		2.5	34.2		5.1	37.7	
Green Ratio (g/C)	0.28	0.28		0.28	0.28		0.57	0.43		0.57	0.43	
Capacity (c), veh/h	222	513		51	504		422	770		450	793	
Volume-to-Capacity Ratio (X)	0.020	1.103		0.827	0.540		0.168	0.697		0.303	0.746	
Back of Queue (Q), ft/ln (50 th percentile)	3.7	709.7		68.2	218.2		28.5	403.8		57.3	462.4	
Back of Queue (Q), veh/ln (50 th percentile)	0.1	27.9		2.7	8.6		1.1	15.9		2.3	18.2	
Queue Storage Ratio (RQ) (50 th percentile)	0.04	0.00		0.68	0.00		0.25	0.00		0.00	0.00	
Uniform Delay (d 1), s/veh	50.7	50.5		70.5	42.7		19.9	33.1		19.8	34.1	
Incremental Delay (d 2), s/veh	0.2	70.8		82.0	4.1		0.9	5.2		1.7	6.3	
Initial Queue Delay (d 3), s/veh	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Control Delay (d), s/veh	50.8	121.3		152.5	46.8		20.7	38.3		21.5	40.4	
Level of Service (LOS)	D	F		F	D		C	D		C	D	
Approach Delay, s/veh / LOS	120.8	F		61.0	E		36.2	D		36.9	D	
Intersection Delay, s/veh / LOS	61.7			E			E			E		

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.3	B	2.3	B	2.3	B	2.3	B
Bicycle LOS Score / LOS	1.4	A	1.0	A	1.5	A	1.7	B

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach	Intersection	Shepherdsville / Famous				
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky				
Date Performed	4/19/2018	East/West Street	Famous Way				
Analysis Year	2018	North/South Street	Shepherdsville Road				
Time Analyzed	Existing PM Peak Hour	Peak Hour Factor	0.90				
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25				
Project Description	Unity Place Apartments TIA						

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	0	0		0	0	0	0	0	1	0	0	0	1	0	
Configuration			LR							LT						TR	
Volume, V (veh/h)		47		112						34	475				708	48	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways


Base Critical Headway (sec)		7.1		6.2							4.1					
Critical Headway (sec)		6.42		6.22							4.12					
Base Follow-Up Headway (sec)		3.5		3.3							2.2					
Follow-Up Headway (sec)		3.52		3.32							2.22					

Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			176								38					
Capacity, c (veh/h)			255								795					
v/c Ratio			0.69								0.05					
95% Queue Length, Q ₉₅ (veh)			4.6								0.2					
Control Delay (s/veh)			45.6								9.8					
Level of Service, LOS			E								A					
Approach Delay (s/veh)		45.6										1.3				
Approach LOS		E														

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach	Intersection	Shepherdsville / Miles				
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky				
Date Performed	4/19/2018	East/West Street	Miles Lane				
Analysis Year	2018	North/South Street	Shepherdsville Road				
Time Analyzed	Existing PM Peak Hour	Peak Hour Factor	0.90				
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25				
Project Description	Unity Place Apartments TIA						



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound							
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R				
Movement																				
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6				
Number of Lanes		0	1	0		0	0	0	0	0	1	0	0	0	1	0				
Configuration			LR							LT							TR			
Volume, V (veh/h)		86		103						37	482					532	186			
Percent Heavy Vehicles (%)		2		2						2										
Proportion Time Blocked																				
Percent Grade (%)		0																		
Right Turn Channelized		No					No					No					No			
Median Type/Storage		Undivided																		

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2							4.1						
Critical Headway (sec)		6.42		6.22							4.12						
Base Follow-Up Headway (sec)		3.5		3.3							2.2						
Follow-Up Headway (sec)		3.52		3.32							2.22						

Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			210								41							
Capacity, c (veh/h)			252								824							
v/c Ratio			0.83								0.05							
95% Queue Length, Q ₉₅ (veh)			6.7								0.2							
Control Delay (s/veh)			64.4								9.6							
Level of Service, LOS			F								A							
Approach Delay (s/veh)		64.4									1.3							
Approach LOS		F									A							


UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Appendix
July 13, 2018

APPENDIX D-3: 2020 NO-BUILD AM

HCS7 Signalized Intersection Results Summary

General Information					Intersection Information	
Agency	Stantec			Duration, h	0.25	
Analyst	M. Peach	Analysis Date	Apr 19, 2018		Area Type	Other
Jurisdiction	Louisville, Kentucky		Time Period	AM Peak Hour	PHF	0.90
Urban Street	Shepherdsville Road		Analysis Year	2020	Analysis Period	1 > 7:00
Intersection	Robbs Lane / Applegate...	File Name	2020_AM_NB_Signal_Intersection1.xus			
Project Description	2020 No-Build AM Peak Hour					



Demand Information	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Approach Movement												
Demand (v), veh/h	4	50	31	59	201	113	54	499	59	31	288	8

Signal Information				Signal Timing (s)						Signal Phases					
Cycle, s	141.0	Reference Phase	2	Green	20.0	60.0	40.0	0.0	0.0	0.0	Green	20.0	60.0	40.0	
Offset, s	0	Reference Point	End	Yellow	5.0	5.0	5.0	0.0	0.0	0.0	Yellow	5.0	5.0	5.0	
Uncoordinated	Yes	Simult. Gap E/W	On	Red	2.0	2.0	2.0	0.0	0.0	0.0	Red	2.0	2.0	2.0	
Force Mode	Fixed	Simult. Gap N/S	On												

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		47.0		47.0	27.0	67.0	27.0	67.0
Change Period, (Y+R _c), s		7.0		7.0	7.0	7.0	7.0	7.0
Max Allow Headway (MAH), s		3.2		3.2	3.1	3.1	3.1	3.1
Queue Clearance Time (g _s), s		27.6		27.0	4.1	43.3	3.2	19.4
Green Extension Time (g _e), s		0.9		0.9	0.1	1.8	0.0	1.9
Phase Call Probability		1.00		1.00	1.00	1.00	1.00	1.00
Max Out Probability		0.00		0.00	0.00	0.01	0.00	0.00


Movement Group Results	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Approach Movement												
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	4	90		66	349		60	620		34	329	
Adjusted Saturation Flow Rate (s), veh/h/ln	1032	1750		1307	1757		1781	1835		1781	1861	
Queue Service Time (g _s), s	0.5	5.5		5.6	25.0		2.1	41.3		1.2	17.4	
Cycle Queue Clearance Time (g _c), s	25.6	5.5		11.1	25.0		2.1	41.3		1.2	17.4	
Green Ratio (g/C)	0.28	0.28		0.28	0.28		0.57	0.43		0.57	0.43	
Capacity (c), veh/h	161	496		371	498		607	781		399	792	
Volume-to-Capacity Ratio (X)	0.028	0.181		0.177	0.700		0.099	0.794		0.086	0.415	
Back of Queue (Q), ft/ln (50 th percentile)	4	62.9		49.1	303.7		23.1	506		13.5	205.5	
Back of Queue (Q), veh/ln (50 th percentile)	0.2	2.5		1.9	12.0		0.9	19.9		0.5	8.1	
Queue Storage Ratio (RQ) (50 th percentile)	0.05	0.00		0.49	0.00		0.20	0.00		0.00	0.00	
Uniform Delay (d ₁), s/veh	56.6	38.1		42.3	45.1		15.1	35.1		20.4	28.3	
Incremental Delay (d ₂), s/veh	0.3	0.8		1.0	8.0		0.3	8.2		0.4	1.6	
Initial Queue Delay (d ₃), s/veh	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Control Delay (d), s/veh	56.9	38.9		43.4	53.1		15.4	43.3		20.8	29.9	
Level of Service (LOS)	E	D		D	D		B	D		C	C	
Approach Delay, s/veh / LOS	39.8		D	51.6		D	40.8		D	29.0		C
Intersection Delay, s/veh / LOS	40.9						D					

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.3	B	2.3	B	2.3	B	2.3	B
Bicycle LOS Score / LOS	0.6	A	1.2	A	1.6	B	1.1	A

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach	Intersection	Shepherdsville / Famous				
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky				
Date Performed	4/19/2018	East/West Street	Famous Way				
Analysis Year	2020	North/South Street	Shepherdsville Road				
Time Analyzed	No-Build AM Peak Hour	Peak Hour Factor	0.90				
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25				
Project Description	Unity Place Apartments TIA						

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	0	0		0	0	0	0	0	1	0	0	0	1	0	
Configuration			LR							LT						TR	
Volume, V (veh/h)		28		17						37	499				255	18	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2							4.1					
Critical Headway (sec)		6.42		6.22							4.12					
Base Follow-Up Headway (sec)		3.5		3.3							2.2					
Follow-Up Headway (sec)		3.52		3.32							2.22					


Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			50								41					
Capacity, c (veh/h)			375								1257					
v/c Ratio			0.13								0.03					
95% Queue Length, Q ₉₅ (veh)			0.5								0.1					
Control Delay (s/veh)			16.1								8.0					
Level of Service, LOS			C								A					
Approach Delay (s/veh)		16.1										0.9				
Approach LOS		C														

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach			Intersection	Shepherdsville / Miles		
Agency/Co.	Stantec			Jurisdiction	Louisville, Kentucky		
Date Performed	4/19/2018			East/West Street	Miles Lane		
Analysis Year	2020			North/South Street	Shepherdsville Road		
Time Analyzed	No-Build AM Peak Hour			Peak Hour Factor	0.90		
Intersection Orientation	North-South			Analysis Time Period (hrs)	0.25		
Project Description	Unity Place Apartments TIA						

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	1	0		0	0	0		0	1	0		0	1	0	
Configuration			LR							LT						TR	
Volume, V (veh/h)		96		19						52	455				294	97	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2						4.1						
Critical Headway (sec)		6.42		6.22						4.12						
Base Follow-Up Headway (sec)		3.5		3.3						2.2						
Follow-Up Headway (sec)		3.52		3.32						2.22						

Delay, Queue Length, and Level of Service


Flow Rate, v (veh/h)			128							58						
Capacity, c (veh/h)			283							1124						
v/c Ratio			0.45							0.05						
95% Queue Length, Q ₉₅ (veh)			2.2							0.2						
Control Delay (s/veh)			27.8							8.4						
Level of Service, LOS			D							A						
Approach Delay (s/veh)		27.8										1.4				
Approach LOS		D														

UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Appendix
July 13, 2018

APPENDIX D-4: 2020 NO-BUILD PM

HCS7 Signalized Intersection Results Summary

General Information					Intersection Information						
Agency	Stantec				Duration, h	0.25					
Analyst	M. Peach	Analysis Date	Apr 19, 2018		Area Type	Other					
Jurisdiction	Louisville, Kentucky	Time Period	PM Peak Hour		PHF	0.90					
Urban Street	Shepherdsville Road	Analysis Year	2020		Analysis Period	1 > 4:00					
Intersection	Robbs Lane / Applegate...	File Name	2020_PM_NB_Signal_Intersection1.xus								
Project Description	2020 No-Build PM Peak Hour										

Demand Information	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Approach Movement												
Demand (v), veh/h	4	432	103	40	182	76	67	411	97	129	551	10

Signal Information													
Cycle, s	141.0	Reference Phase	2										
Offset, s	0	Reference Point	End										
Uncoordinated	Yes	Simult. Gap E/W	On	Green	20.0	60.0	40.0	0.0	0.0	0.0			
				Yellow	5.0	5.0	5.0	0.0	0.0	0.0			
Force Mode	Fixed	Simult. Gap N/S	On	Red	2.0	2.0	2.0	0.0	0.0	0.0			

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		47.0		47.0	27.0	67.0	27.0	67.0
Change Period, (Y+R _c), s		7.0		7.0	7.0	7.0	7.0	7.0
Max Allow Headway (MAH), s		3.2		3.2	3.1	3.1	3.1	3.1
Queue Clearance Time (g _s), s		42.0		42.0	4.7	38.8	7.3	42.7
Green Extension Time (g _e), s		0.0		0.0	0.1	2.5	0.2	2.4
Phase Call Probability		1.00		1.00	1.00	1.00	1.00	1.00
Max Out Probability		1.00		1.00	0.00	0.01	0.00	0.02

Movement Group Results	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	4	594		44	287		74	564		143	623	
Adjusted Saturation Flow Rate (s), veh/h/ln	1093	1808		823	1776		1781	1808		1781	1864	
Queue Service Time (g _s), s	0.5	40.0		0.0	19.4		2.7	36.8		5.3	40.7	
Cycle Queue Clearance Time (g _c), s	19.9	40.0		40.0	19.4		2.7	36.8		5.3	40.7	
Green Ratio (g/C)	0.28	0.28		0.28	0.28		0.57	0.43		0.57	0.43	
Capacity (c), veh/h	210	513		51	504		402	769		431	793	
Volume-to-Capacity Ratio (X)	0.021	1.159		0.870	0.569		0.185	0.734		0.332	0.786	
Back of Queue (Q), ft/ln (50 th percentile)	3.7	784.8		73.8	232.8		30	437.1		60.8	504	
Back of Queue (Q), veh/ln (50 th percentile)	0.1	30.9		2.9	9.2		1.2	17.2		2.4	19.8	
Queue Storage Ratio (RQ) (50 th percentile)	0.04	0.00		0.74	0.00		0.26	0.00		0.00	0.00	
Uniform Delay (d ₁), s/veh	51.6	50.5		70.5	43.1		20.9	33.8		20.8	35.0	
Incremental Delay (d ₂), s/veh	0.2	91.6		91.9	4.6		1.0	6.1		2.1	7.7	
Initial Queue Delay (d ₃), s/veh	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Control Delay (d), s/veh	51.8	142.1		162.4	47.7		21.9	40.0		22.8	42.7	
Level of Service (LOS)	D	F		F	D		C	D		C	D	
Approach Delay, s/veh / LOS	141.4	F		63.1	E		37.8	D		38.9	D	
Intersection Delay, s/veh / LOS	68.4						E					

Multimodal Results	EB			WB			NB			SB		
Pedestrian LOS Score / LOS	2.3	B		2.3	B		2.3	B		2.3	B	
Bicycle LOS Score / LOS	1.5	A		1.0	A		1.5	B		1.8	B	


HCS7 Two-Way Stop-Control Report

General Information

Site Information

Analyst	M. Peach	Intersection	Shepherdsville / Famous
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky
Date Performed	4/19/2018	East/West Street	Famous Way
Analysis Year	2020	North/South Street	Shepherdsville Road
Time Analyzed	No-Build PM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	Unity Place Apartments TIA		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	0	0		0	0	0		0	1	0		0	1	0	
Configuration			LR							LT						TR	
Volume, V (veh/h)		49		118						36	499				744	50	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2							4.1					
Critical Headway (sec)		6.42		6.22							4.12					
Base Follow-Up Headway (sec)		3.5		3.3							2.2					
Follow-Up Headway (sec)		3.52		3.32							2.22					


Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			185								40					
Capacity, c (veh/h)			236								766					
v/c Ratio			0.78								0.05					
95% Queue Length, Q ₉₅ (veh)			5.7								0.2					
Control Delay (s/veh)			59.6								10.0					
Level of Service, LOS			F								A					
Approach Delay (s/veh)		59.6										1.4				
Approach LOS		F														

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach	Intersection	Shepherdsville / Miles				
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky				
Date Performed	4/19/2018	East/West Street	Miles Lane				
Analysis Year	2020	North/South Street	Shepherdsville Road				
Time Analyzed	No-Build PM Peak Hour	Peak Hour Factor	0.90				
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25				
Project Description	Unity Place Apartments TIA						

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	1	0		0	0	0		0	1	0		0	0	1	
Configuration			LR							LT						TR	
Volume, V (veh/h)		91		108						39	507				559	195	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)																	
Critical Headway (sec)																	
Base Follow-Up Headway (sec)																	
Follow-Up Headway (sec)																	

Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			221							43							
Capacity, c (veh/h)			232							796							
v/c Ratio			0.95							0.05							
95% Queue Length, Q ₉₅ (veh)			8.5							0.2							
Control Delay (s/veh)			92.4							9.8							
Level of Service, LOS			F							A							
Approach Delay (s/veh)		92.4										1.4					
Approach LOS		F															


UNITY PLACE APARTMENTS TRAFFIC IMPACT ANALYSIS

Appendix
July 13, 2018

APPENDIX D-5: 2020 BUILD AM

HCS7 Signalized Intersection Results Summary

General Information				Intersection Information			
Agency	Stantec			Duration, h	0.25		
Analyst	M. Peach		Analysis Date	Apr 19, 2018		Area Type	Other
Jurisdiction	Louisville, Kentucky		Time Period	AM Peak Hour		PHF	0.90
Urban Street	Shepherdsville Road		Analysis Year	2020		Analysis Period	1 > 7:00
Intersection	Robbs Lane / Applegate...		File Name	2020_AM_B_Signal_Intersection1.xus			
Project Description	2020 Build AM Peak Hour						



Demand Information	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Approach Movement												
Demand (v), veh/h	4	50	34	61	201	113	61	522	65	31	296	8

Signal Information													
Cycle, s	141.0	Reference Phase	2										
Offset, s	0	Reference Point	End										
Uncoordinated	Yes	Simult. Gap E/W	On	Green	20.0	60.0	40.0	0.0	0.0	0.0			
Force Mode	Fixed	Simult. Gap N/S	On	Yellow	5.0	5.0	5.0	0.0	0.0	0.0			
				Red	2.0	2.0	2.0	0.0	0.0	0.0			

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		47.0		47.0	27.0	67.0	27.0	67.0
Change Period, (Y+Rc), s		7.0		7.0	7.0	7.0	7.0	7.0
Max Allow Headway (MAH), s		3.2		3.2	3.1	3.1	3.1	3.1
Queue Clearance Time (gs), s		27.6		27.0	4.4	46.7	3.2	20.0
Green Extension Time (ge), s		0.9		0.9	0.1	1.9	0.0	2.0
Phase Call Probability		1.00		1.00	1.00	1.00	1.00	1.00
Max Out Probability		0.00		0.00	0.00	0.03	0.00	0.00

Movement Group Results	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	4	93		68	349		68	652		34	338	
Adjusted Saturation Flow Rate (s), veh/h/ln	1032	1743		1303	1757		1781	1834		1781	1862	
Queue Service Time (gs), s	0.5	5.7		5.9	25.0		2.4	44.7		1.2	18.0	
Cycle Queue Clearance Time (gc), s	25.6	5.7		11.6	25.0		2.4	44.7		1.2	18.0	
Green Ratio (g/C)	0.28	0.28		0.28	0.28		0.57	0.43		0.57	0.43	
Capacity (c), veh/h	161	495		368	498		600	780		377	792	
Volume-to-Capacity Ratio (X)	0.028	0.189		0.184	0.700		0.113	0.836		0.091	0.426	
Back of Queue (Q), ft/ln (50 th percentile)	4	65.4		51.1	303.7		26.2	555.1		13.5	212.4	
Back of Queue (Q), veh/ln (50 th percentile)	0.2	2.6		2.0	12.0		1.0	21.9		0.5	8.4	
Queue Storage Ratio (RQ) (50 th percentile)	0.05	0.00		0.51	0.00		0.23	0.00		0.00	0.00	
Uniform Delay (d1), s/veh	56.6	38.2		42.6	45.1		15.2	36.1		21.5	28.4	
Incremental Delay (d2), s/veh	0.3	0.8		1.1	8.0		0.4	10.3		0.5	1.7	
Initial Queue Delay (d3), s/veh	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Control Delay (d), s/veh	56.9	39.1		43.7	53.1		15.6	46.4		22.0	30.1	
Level of Service (LOS)	E	D		D	D		B	D		C	C	
Approach Delay, s/veh / LOS	39.9		D	51.6		D	43.5		D	29.4		C
Intersection Delay, s/veh / LOS	42.1						D					

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.3	B	2.3	B	2.3	B	2.3	B
Bicycle LOS Score / LOS	0.6	A	1.2	A	1.7	B	1.1	A


HCS7 Two-Way Stop-Control Report

General Information

Site Information

Analyst	M. Peach	Intersection	Shepherdsville / Famous
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky
Date Performed	4/19/2018	East/West Street	Famous Way
Analysis Year	2020	North/South Street	Shepherdsville Road
Time Analyzed	Build AM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	Unity Place Apartments TIA		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound							
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R				
Movement																				
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6				
Number of Lanes		0	0	0		0	0	0	0	0	1	0	0	0	1	0				
Configuration			LR							LT							TR			
Volume, V (veh/h)		28		17						37	509					285	18			
Percent Heavy Vehicles (%)		2		2						2										
Proportion Time Blocked																				
Percent Grade (%)		0																		
Right Turn Channelized		No					No					No					No			
Median Type/Storage		Undivided																		

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2										4.1				
Critical Headway (sec)		6.42		6.22										4.12				
Base Follow-Up Headway (sec)		3.5		3.3										2.2				
Follow-Up Headway (sec)		3.52		3.32										2.22				


Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			50											41				
Capacity, c (veh/h)			353											1221				
v/c Ratio			0.14											0.03				
95% Queue Length, Q ₉₅ (veh)			0.5											0.1				
Control Delay (s/veh)			16.9											8.0				
Level of Service, LOS			C											A				
Approach Delay (s/veh)		16.9									0.9							
Approach LOS		C																

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach	Intersection	Shepherdsville / Miles				
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky				
Date Performed	4/19/2018	East/West Street	Miles Lane				
Analysis Year	2020	North/South Street	Shepherdsville Road				
Time Analyzed	Build AM Peak Hour	Peak Hour Factor	0.90				
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25				
Project Description	Unity Place Apartments TIA						

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	0	0		0	0	0	0	0	1	0	0	0	1	0	
Configuration			LR							LT						TR	
Volume, V (veh/h)		98		19						52	463				317	104	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2							4.1					
Critical Headway (sec)		6.42		6.22							4.12					
Base Follow-Up Headway (sec)		3.5		3.3							2.2					
Follow-Up Headway (sec)		3.52		3.32							2.22					


Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			130								58						
Capacity, c (veh/h)			269								1093						
v/c Ratio			0.48								0.05						
95% Queue Length, Q ₉₅ (veh)			2.5								0.2						
Control Delay (s/veh)			30.4								8.5						
Level of Service, LOS			D								A						
Approach Delay (s/veh)		30.4									1.4						
Approach LOS		D															

HCS7 Two-Way Stop-Control Report

General Information		Site Information	
Analyst	M. Peach	Intersection	Shepherdsville / Access A
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky
Date Performed	4/19/2018	East/West Street	Site Access A
Analysis Year	2020	North/South Street	Shepherdsville Road
Time Analyzed	Build AM Peak Hour	Peak Hour Factor	0.90
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25
Project Description	Unity Place Apartments TIA		

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	1	0		0	0	0	0	1	1	0	0	0	1	1	
Configuration			LR							L	T				T	R	
Volume, V (veh/h)		16		13						5	632				385	6	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)																	
Critical Headway (sec)																	
Base Follow-Up Headway (sec)																	
Follow-Up Headway (sec)																	


Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)		32								6							
Capacity, c (veh/h)		308								1124							
v/c Ratio		0.10								0.01							
95% Queue Length, Q ₉₅ (veh)		0.3								0.0							
Control Delay (s/veh)		18.1								8.2							
Level of Service, LOS		C								A							
Approach Delay (s/veh)		18.1								0.1							
Approach LOS		C															

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach	Intersection	Shepherdsville / Access B				
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky				
Date Performed	4/19/2018	East/West Street	Site Access B				
Analysis Year	2020	North/South Street	Shepherdsville Road				
Time Analyzed	Build AM Peak Hour	Peak Hour Factor	0.90				
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25				
Project Description	Unity Place Apartments TIA						

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound					
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R		
Movement																		
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6		
Number of Lanes		0	0	0		0	0	0		0	1	1	0		0	0	1	1
Configuration			LR							L	T					T	R	
Volume, V (veh/h)		20		17						5	617					391	7	
Percent Heavy Vehicles (%)		2		2						2								
Proportion Time Blocked																		
Percent Grade (%)		0																
Right Turn Channelized		No					No					No						
Median Type/Storage		Undivided																

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2							4.1						
Critical Headway (sec)		6.42		6.22							4.12						
Base Follow-Up Headway (sec)		3.5		3.3							2.2						
Follow-Up Headway (sec)		3.52		3.32							2.22						

Delay, Queue Length, and Level of Service


Flow Rate, v (veh/h)			41								6						
Capacity, c (veh/h)			318								1117						
v/c Ratio			0.13								0.01						
95% Queue Length, Q ₉₅ (veh)			0.4								0.0						
Control Delay (s/veh)			18.0								8.2						
Level of Service, LOS			C								A						
Approach Delay (s/veh)		18.0										0.1					
Approach LOS		C															

Appendix
July 13, 2018

APPENDIX D-6: 2020 BUILD PM

HCS7 Signalized Intersection Results Summary

General Information				Intersection Information			
Agency	Stantec			Duration, h	0.25		
Analyst	M. Peach	Analysis Date	Apr 19, 2018	Area Type	Other		
Jurisdiction	Louisville, Kentucky	Time Period	PM Peak Hour	PHF	0.90		
Urban Street	Shepherdsville Road	Analysis Year	2020	Analysis Period	1 > 4:00		
Intersection	Robbs Lane / Applegate...	File Name	2020_PM_B_Signal_Intersection1.xus				
Project Description	2020 Build PM Peak Hour						



Demand Information	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Approach Movement												
Demand (v), veh/h	4	432	110	47	182	76	70	426	101	129	575	10

Signal Information													
Cycle, s	141.0	Reference Phase	2										
Offset, s	0	Reference Point	End										
Uncoordinated	Yes	Simult. Gap E/W	On	Green	20.0	60.0	40.0	0.0	0.0	0.0			
Force Mode	Fixed	Simult. Gap N/S	On	Yellow	5.0	5.0	5.0	0.0	0.0	0.0			
				Red	2.0	2.0	2.0	0.0	0.0	0.0			

Timer Results	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Assigned Phase		4		8	5	2	1	6
Case Number		6.0		6.0	1.1	4.0	1.1	4.0
Phase Duration, s		47.0		47.0	27.0	67.0	27.0	67.0
Change Period, (Y+R _c), s		7.0		7.0	7.0	7.0	7.0	7.0
Max Allow Headway (MAH), s		3.2		3.2	3.1	3.1	3.1	3.1
Queue Clearance Time (g _s), s		42.0		42.0	4.8	40.8	7.3	45.3
Green Extension Time (g _e), s		0.0		0.0	0.1	2.6	0.2	2.5
Phase Call Probability		1.00		1.00	1.00	1.00	1.00	1.00
Max Out Probability		1.00		1.00	0.00	0.01	0.00	0.05


Movement Group Results	EB			WB			NB			SB		
	L	T	R	L	T	R	L	T	R	L	T	R
Assigned Movement	7	4	14	3	8	18	5	2	12	1	6	16
Adjusted Flow Rate (v), veh/h	4	602		52	287		78	586		143	650	
Adjusted Saturation Flow Rate (s), veh/h/ln	1093	1804		817	1776		1781	1808		1781	1865	
Queue Service Time (g _s), s	0.5	40.0		0.0	19.4		2.8	38.8		5.3	43.3	
Cycle Queue Clearance Time (g _c), s	19.9	40.0		40.0	19.4		2.8	38.8		5.3	43.3	
Green Ratio (g/C)	0.28	0.28		0.28	0.28		0.57	0.43		0.57	0.43	
Capacity (c), veh/h	210	512		51	504		385	769		417	793	
Volume-to-Capacity Ratio (X)	0.021	1.176		1.023	0.569		0.202	0.761		0.344	0.819	
Back of Queue (Q), ft/ln (50 th percentile)	3.7	807.7		94.5	232.8		31.6	464.3		61.1	542.9	
Back of Queue (Q), veh/ln (50 th percentile)	0.1	31.8		3.7	9.2		1.2	18.3		2.4	21.4	
Queue Storage Ratio (RQ) (50 th percentile)	0.04	0.00		0.95	0.00		0.28	0.00		0.00	0.00	
Uniform Delay (d ₁), s/veh	51.6	50.5		70.5	43.1		21.9	34.4		21.5	35.7	
Incremental Delay (d ₂), s/veh	0.2	98.3		132.6	4.6		1.2	7.0		2.2	9.2	
Initial Queue Delay (d ₃), s/veh	0.0	0.0		0.0	0.0		0.0	0.0		0.0	0.0	
Control Delay (d), s/veh	51.8	148.8		203.1	47.7		23.1	41.4		23.7	44.9	
Level of Service (LOS)	D	F		F	D		C	D		C	D	
Approach Delay, s/veh / LOS	148.1		F	71.7		E	39.3		D	41.1		D
Intersection Delay, s/veh / LOS	71.9						E					

Multimodal Results	EB		WB		NB		SB	
Pedestrian LOS Score / LOS	2.3	B	2.3	B	2.3	B	2.3	B
Bicycle LOS Score / LOS	1.5	A	1.0	A	1.6	B	1.8	B

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach	Intersection	Shepherdsville / Famous				
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky				
Date Performed	4/19/2018	East/West Street	Famous Way				
Analysis Year	2020	North/South Street	Shepherdsville Road				
Time Analyzed	Build PM Peak Hour	Peak Hour Factor	0.90				
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25				
Project Description	Unity Place Apartments TIA						

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	0	0		0	0	0		0	1	0		0	1	0	
Configuration			LR							LT						TR	
Volume, V (veh/h)		49		118						36	530				764	50	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2						4.1						
Critical Headway (sec)		6.42		6.22						4.12						
Base Follow-Up Headway (sec)		3.5		3.3						2.2						
Follow-Up Headway (sec)		3.52		3.32						2.22						


Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			185							40						
Capacity, c (veh/h)			223							751						
v/c Ratio			0.83							0.05						
95% Queue Length, Q ₉₅ (veh)			6.3							0.2						
Control Delay (s/veh)			69.4							10.1						
Level of Service, LOS			F							B						
Approach Delay (s/veh)		69.4										1.4				
Approach LOS		F														

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach	Intersection	Shepherdsville / Miles				
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky				
Date Performed	4/19/2018	East/West Street	Miles Lane				
Analysis Year	2020	North/South Street	Shepherdsville Road				
Time Analyzed	Build PM Peak Hour	Peak Hour Factor	0.90				
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25				
Project Description	Unity Place Apartments TIA						

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound							
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R				
Movement																				
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6				
Number of Lanes		0	0	0		0	0	0	0	0	1	0	0	0	1	0				
Configuration			LR							LT						TR				
Volume, V (veh/h)		98		108						39	531				574	200				
Percent Heavy Vehicles (%)		2		2						2										
Proportion Time Blocked																				
Percent Grade (%)		0																		
Right Turn Channelized		No					No					No					No			
Median Type/Storage		Undivided																		

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2							4.1						
Critical Headway (sec)		6.42		6.22							4.12						
Base Follow-Up Headway (sec)		3.5		3.3							2.2						
Follow-Up Headway (sec)		3.52		3.32							2.22						

Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			229								43							
Capacity, c (veh/h)			215								781							
v/c Ratio			1.06								0.06							
95% Queue Length, Q ₉₅ (veh)			10.2								0.2							
Control Delay (s/veh)			126.7								9.9							
Level of Service, LOS			F								A							
Approach Delay (s/veh)		126.7									1.4							
Approach LOS		F									A							

HCS7 Two-Way Stop-Control Report


General Information

Analyst	M. Peach
Agency/Co.	Stantec
Date Performed	4/19/2018
Analysis Year	2020
Time Analyzed	Build PM Peak Hour
Intersection Orientation	North-South
Project Description	Unity Place Apartments TIA

Site Information

Intersection	Shepherdsville / Access A
Jurisdiction	Louisville, Kentucky
East/West Street	Site Access A
North/South Street	Shepherdsville Road
Peak Hour Factor	0.90
Analysis Time Period (hrs)	0.25

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	0	0		0	0	0		0	1	1		0	0	1	
Configuration			LR							L	T				T	R	
Volume, V (veh/h)		11		9						14	588				714	17	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2						4.1						
Critical Headway (sec)		6.42		6.22						4.12						
Base Follow-Up Headway (sec)		3.5		3.3						2.2						
Follow-Up Headway (sec)		3.52		3.32						2.22						


Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			22							16						
Capacity, c (veh/h)			193							814						
v/c Ratio			0.11							0.02						
95% Queue Length, Q ₉₅ (veh)			0.4							0.1						
Control Delay (s/veh)			26.0							9.5						
Level of Service, LOS			D							A						
Approach Delay (s/veh)		26.0										0.2				
Approach LOS		D														

HCS7 Two-Way Stop-Control Report

General Information				Site Information			
Analyst	M. Peach	Intersection	Shepherdsville / Access B				
Agency/Co.	Stantec	Jurisdiction	Louisville, Kentucky				
Date Performed	4/19/2018	East/West Street	Site Access B				
Analysis Year	2020	North/South Street	Shepherdsville Road				
Time Analyzed	Build PM Peak Hour	Peak Hour Factor	0.90				
Intersection Orientation	North-South	Analysis Time Period (hrs)	0.25				
Project Description	Unity Place Apartments TIA						

Lanes



Vehicle Volumes and Adjustments

Approach	Eastbound				Westbound				Northbound				Southbound				
	U	L	T	R	U	L	T	R	U	L	T	R	U	L	T	R	
Movement																	
Priority		10	11	12		7	8	9	1U	1	2	3	4U	4	5	6	
Number of Lanes		0	0	0		0	0	0		0	1	1	0	0	0	1	
Configuration			LR							L	T				T	R	
Volume, V (veh/h)		13		11						17	589				702	21	
Percent Heavy Vehicles (%)		2		2						2							
Proportion Time Blocked																	
Percent Grade (%)		0															
Right Turn Channelized		No					No					No					
Median Type/Storage		Undivided															

Critical and Follow-up Headways

Base Critical Headway (sec)		7.1		6.2							4.1					
Critical Headway (sec)		6.42		6.22							4.12					
Base Follow-Up Headway (sec)		3.5		3.3							2.2					
Follow-Up Headway (sec)		3.52		3.32							2.22					

Delay, Queue Length, and Level of Service

Flow Rate, v (veh/h)			26								19					
Capacity, c (veh/h)			196								820					
v/c Ratio			0.13								0.02					
95% Queue Length, Q ₉₅ (veh)			0.5								0.1					
Control Delay (s/veh)			26.2								9.5					
Level of Service, LOS			D								A					
Approach Delay (s/veh)		26.2										0.3				
Approach LOS		D														