

Included in the work provided is the following:

Tension Backstop Netting System: Features include Ultra Cross Knotless Dyneema 1.2mm knotless profile, 316lb minimum straight line break strength, 100% twine tenacity, excellent resistance to UV light, chemicals and water.

- Remove current backstop and cabling system
- Install steel coated poles
- Install new main cable
- Install six tie back cables
- Install new Ultra Cross Dyneema (266' x 30')
- Engineering of loads

Stadium Field Padding:

Replace old pads with BaseZone Field Wall Padding, EcoGuard 18 oz. UV Resistant Extruded Vinyl, 3" Thick High Impact Polyurethane Foam, 3/4" Square Edged Composite Sheathing, Stainless Steel Fasteners, Z Clip Wall mounting system. Includes all wall padding consistent with current stadium layout consisting of backstop, sidelines, and outfield padding. Includes 8" vinyl strip consistent with current layout.

Replace guard rail around dugouts with Standard Guard Rail Padding, 18 oz. UV Resistant Extruded Vinyl, 1" Thick High Impact Polyurethane Foam, Fits up to 2" Diameter Rails, Two (2) -1.5 Wide Vinyl Flaps with #2 Stainless Steel Grommets Factory Inserted Every 6" on Center for Attached Purposes. Rail Padding Consistent with current rail layout. Includes replacement infill netting for both dugouts.

All padding work includes install, removal and disposal and freight.