



PIPE CHART

PIPE NO.	AREA ac	RUNOFF COEFF.	SUM C*A	TIME CONC. min	I 10 YR. in/hr	I 100 YR in/hr	Q 10 YR cfs	Q 100 YR cfs	PIPE SIZE in	PIPE LENGTH ft	PIPE SLOPE ft/ft	VEL. 10 YR fps	HW 10 YR ft	HW 100 YR ft	PIPE CAPACITY cfs
1	0.74	0.95	0.70	10.00	5.30	7.20	3.7	5.1	15	64	0.0060	4.7	1.2	4.5	5.4
2	0.00	0.95	0.78	10.22	5.25	7.13	4.1	5.6	15	75	0.0070	5.1	1.3	1.5	5.9
3	0.00	0.95	0.78	10.47	5.20	7.08	4.1	5.5	15	149	0.0070	5.1	1.3	1.6	5.9
4	0.00	0.95	0.78	10.95	5.09	6.93	4.0	5.4	15	81	0.0070	5.1	1.3	1.6	5.9
5.1	0.12	0.95	0.89	11.22	5.04	6.86	4.5	6.1	18	47	0.0050	4.7	1.2	1.5	8.0
5.2	0.00	0.95	0.89	11.38	5.01	6.82	4.5	6.1	18	6	0.0050	4.7	1.2	1.5	8.0
6	0.00	0.95	1.49	11.41	5.00	6.82	7.5	10.2	18	4	0.0100	6.8	1.7	2.3	11.4
7	0.08	0.95	0.08	10.00	5.30	7.20	0.4	0.5	12	5	0.0050	2.5	0.3	0.4	2.7
8	0.58	0.95	0.55	10.00	5.30	7.20	2.9	4.0	15	63	0.0050	4.2	1.0	1.3	4.9
9.1	0.05	0.95	0.60	10.25	5.24	7.12	3.1	4.3	15	242	0.0050	4.2	1.1	1.3	4.9
9.2	0.00	0.95	0.60	11.20	5.04	6.87	3.0	4.1	15	9	0.0050	4.2	1.0	1.3	4.9
10	0.00	0.95	0.60	11.24	5.04	6.86	3.0	4.1	15	17	0.0050	4.2	1.0	1.3	4.9

	MSD STANDARD EROSION CONTROL	S
-D ^{SF}	SILT FENCE	EF-09-02
1	CONSTRUCTION ENTRANCE	ER-01-03
2	FILTER FABRIC INLET PROTECTION	EF-01-02
3	STONE BAG INLET PROTECTION	EF-03-01

RECEIVED

JUN 2 0 2016

- LAIVINING O **DESIGN SERVICES**

Proposed location for Awning / building sign

PHASING AND SEQUENCING

- Contractor to sewcut and remove existing povernent and sidewalk to the extent necessary
 to install slit fence. Slit fence to be placed just inside existing curb along Floyd.
- Contractor to utilize existing povement as construction entrance.
- Contractor to removed existing on-site storm sever and cap at property line if necessary per all MSD specifications, ensuring no infiltration of sediment into pipe.
- 4. Contractor to coordinate with LG&E for the removal of site electric and gas services.
- Contractor to clear and grub all trees and brush, disposing of material offsite. All sediment being created from this process to be directed to a BMP.
- Contractor to commence with powement, buildings, and sidewalk demolition ensuring any sediment is directed to the sitt fence. Sidewalk demolition to stop where indicated on plan. Existing powement may be left at the contractor's discretion for construction stoging.
- Contractor to remove existing storm system (cap where needed per MSD specification and mass grade site as needed ensuring all sediment is directed to a BMP. Contractor to excavate for and install underground detention system including tie-in to the public system, per all MSD specifications.
- O Contractor to Install permanent pipe system and connect to underground detention system when necessary. Contractor to ensure public system tit—in has been fully installed per all MSD standards before installing and connecting permanent pipe system. Immediately following pipe system construction, stone bag inlet protection to be placed on all Inlets as Indicated.
- Contractor to construct all building foundations. At contractor's discretion, building foundation construction maybe be done in conjunction with permanent pipe system and underground detention system.
- Upon completion of foundation, contractor to complete foundation certification and provide to MSD to obtain full approvals.
- 13. Contractor to proceed with construction of pavement and hardscape.
- 14. Once area draining to right-of-way is atabilized, contractor to remove sections of silt fence and relocate construction fencing if necessary to sancul, remove, and rebuild indicated curb and any remaining public sidewalk including permanent entrancé oprons. If sile is atabilized by 80%, silt fence does not need to be re-located.
- Once site is stabilized, contractor to remove all BMP's and all accumulated sediment in the underground detention system.
- 16. Each BMP shown on the Erosion Prevention & Sediment Control Plan must be inspected and noted by the EPSC Certified inspector every 7 colendor days & within 24 hours of a half inch or greater storm event.

Proposed location for Preestanding

EROSION PREVENTION AND SEDIMENT CONTROL NOTES
THE APPROVED EROSION PREVENTION AND SEDMENT CONTROL (EPSC) PLAN
SHALL BE IMPLEMENTED PRIOR TO ANY LAND-DISTURBING ACTIVITY ON THE
CONSTRUCTION STEE ANY MODIFICATIONS TO THE APPROVED PESC PLAN
MUST BE REVIEWED AND APPROVED BY MSD'S PRIVATE DEVELOPMENT REVIEW
OFFICE. EPSC BMP'S (BEST MANAGEMENT PRACTICES) SHALL BE INSTALLED
PER THE PLAN AND MSD STANDARDS.

DETENTION BASINS, IF APPLICABLE, SHALL BE CONSTRUCTED FIRST AND SHALL PERFORM AS SEDMENT BASINS DURING CONSTRUCTION UNTIL THE CONTRIBUTING DRAINAGE AREAS ARE SEEDED AND STRAILIZED.

ACTIONS MUST BE TAKEN TO MINIMIZE THE TRACKING OF MUD AND SOIL FROM CONSTRUCTION AND SOIL FROM CONSTRUCTION AREAS ONTO PUBLIC ROADWAYS. SOIL TRACKED ONTO THE ROADWAY SHALL BE REMOVED DAILY.

SOIL STOCKPILES SHALL BE LOCATED AWAY FROM STREAMS, PONDS, SWALES, AND CATCH BASINS. STOCKPILES SHALL BE SEEDED, MULCHED, AND ADEQUATELY CONTAINED THROUGH THE USE OF SILT FENGE.

ALL STREAM CROSSINGS MUST UTILIZE LOW-WATER CROSSING STRUCTURES PER MSD STANDARD DRAWING ER-02.

SEDIMENT-LADEN GROUNDWATER ENCOUNTERED DURING TRENCHING, BORING OR OTHER EXCAVATION ACTIVITIES SHALL BE PUMPED TO A SEDIMENT TRAPPING DEVICE PRIOR TO BEING DISCHARGED INTO A STREAM, POND, SWALE, OR CATCH BASIN.

WHERE CONSTRUCTION OR LAND DISTURBING ACTIVITY WILL OR HAS TEMPORARILY CEASED ON ANY PORTION OF A STIE, TEMPORARY SITE STABILIZATION MEASURES SHALL BE REQUIRED AS SOON AS PRACTICABLE, BUT NO LATER THAN 14 DAYS AFTER THE ACTIVITY HAS CEASED.



UTILITY NOTE: ALL UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE THE INDIVIDUAL SERVICE LINES ARE NOT SHOWN. THE CONTRACTOR OR SUBCONTRACTOR SHALL NOTIFY THE UTILITY PROTECTION CENTER, "KENTUCKY BY "(TOLL FREE PHONE NO. 1-BOO-725-BOOT OR LOCAL NO. 502-268-5123) FORTY EIGHT HOURS IN ADVANCE OF ANY CONSTRUCTION ON THIS PROJECT. HIS NUMBER WAS ESTABLISHED TO PROVIDE ACCURATE LOCATIONS OF EXISTING BELOW GROUND UTILITIES (I.E. CABLES, ELECTRIC WRES, CAS, AND WATERLINES). WHEN CONTACTING THE "KENTUCKY BIT" CALL CENTER, PLEASE STATE THAT THE WORN TO BE DONE IS FOR A PROPUSED MSD SEWER OR TRAINAGE FACILITY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR BECOMINE FAMILIAR WITH ALL UTILITY REQUIREMENTS SET FORTH ON THE PLANS IN THE TECHNICAL SPECIFICATIONS AND SPECIAL PROVISIONS.

WM # 9749 WM# 9749

Treatment of the last		1	BY	DLR	DLR	DLR	OLR	EJB	D	7/21/2015
	REVISIONS		DESCRIP TION	AGENCY SUBMITTAL	AGENCY COMMENTS	STREETSCAPE REVISIONS	APPROVAL SUBMITTAL	WALL REVISION		7/21/2015 1:36:17 PM
With the second contract of the second contrac			DATE	3-12-14	4-8-14	11-3-14	11-20-14	01-05-15		REVISION #E 8/D SET
			NO.	-	2	2	4	2		
									SURVEYOR'S SEAL	and the second s
	Mile	COS KEL	A ERRES O	de China	-4. PE 23759 a	ON SICENSES IN	The state of the s		ENGINEER'S SEAL	
	PRO ECT DATA		(FILE NAME: 07012~2 - GR0		(DATE: 3-5-14) (SCALE: AS SHOWN)		CHECKED BY: EB DRAWN BY: DLR			
					LAND DESIGN & DEVELOPMENT, INC.	ENGINEERING - LAND SIRVEYING - LANDSCAPE ARCHITECTURE	SOS WASHURN ANENE, SLITE OF LAUSHALL, KUNTUKY AOZZZ	WED SITE: WWWILD-NECOM		
	SITE GRADING, EPSC, & CDP	THE MINE AT I CHEWILLE			OWNER/DEVELOPER	SOS DEVELOPMENT GROUP	2209 EAST 7TH AVENUE STE. C	TAMPA, FL 33605		

JOS NO.

