BK37 X Pg 101

CERTIFICATE OF OWNERSHIP AND DEDICATION

This is to certify that the undersigned is the owner of the land shown on this plat and hereby acknowledges the same to be the plat of GLENMARY and does hereby dedicate to public use the DRIVE AND COURT shown thereon.

OWNERS: William T. Hinton
PRESIDENT

CERTIFICATE OF ACKNOWLEDGMENT

STATE OF KENTUCKY
COUNTY OF JEFFERSON ss

I, DONALD A. RUSSELL, a Notary Public in and for the County aforesaid do hereby certify that the foregoing plat of GLENMARY was this day presented to me by WILLIAM T. HINTON known to me, who executed the Certificate in my presence and acknowledged it to be HIS free act and deed.

Witness my hand and seal this 31st day of JAN 19 90.
My Commission expires 28th day of FEB 19 91.
Donald A. Russell
Notary Public

CERTIFICATE OF APPROVAL

Approved this 14th day of March 19 90
LOUISVILLE AND JEFFERSON COUNTY PLANNING COMMISSION
Charles Francis

CERTIFICATE OF RESERVATION OF ELECTRIC & TELEPHONE EASEMENTS

The spaces outlined in dashed lines and marked "electric and telephone easement" are hereby reserved as easements for electric and telephone cable purposes, which include: (1) the right of ingress and egress across all lots, across streets, and were to arise from the assignments; (2) the right to cut down or trim any trees within the easements; (3) the right to trim or cut down any trees outside easement area within 10' of the electric connection where the easement as a radial entry on the right to cut down or trim any trees on private property that may be or become so as to interfere or become in the electric lines under maximum sweep or may property owner; (3) the right of any utility company whose sole easement is to remove permanent structures or obstructions within the easements, but permanent structures should be erected within the easement. Fences, shrubbery and garages may occupy easement area at the property owner's risk. The developer or his heirs or may not interfere with the proper construction of the electric lines and telephone lines to serve the subdivision.

(A) All property owners receive utility service lines shall be underground in accordance with the Louisville Gas and Electric Company (then L.G.&E.) underground service regulations before any service lines to customer's buildings, and the owner shall agree with the then owner of, and the user of, installation and maintenance thereof shall be borne individually by the residential or owner upon which the said service line is located.

Accessories easements are to open accessible and reserved to each property owner, together with the rights of ingress and egress over abutting lots or properties for such purposes, and the said owner of each lot shall keep the area of the easement on his property free of obstructions so as to permit access at all times by the utility company for the purpose of installing, maintaining, removing or replacing said service line.

(B) The electric and telephone easements shown on this plat shall be maintained and operated in their present condition and no encroachment thereon and no change in the grade of elevation thereof shall be made by any person or any property without the consent in writing of the Louisville Gas and Electric Company and South Central Bell Telephone Company.

(C) Easements for overhead electric transmission and distribution feeder lines, poles and equipment appurtenant to connection therewith are reserved over across and under all streets designated POR, down and alongside POR'S as shown, and to down lines and easements for underground and overhead service.

Above ground electric transformers and pedestals may be installed at appropriate points in this easement.

In consideration of L.G.&E. providing service in the property shown on this plat it is granted the right to make normal additions to its lines from all overhead and underground distribution lines.

(D) Above ground electrical installations and pedestals may be installed at appropriate points in this easement.

NOTE
Lots are now or hereafter served with gaseous fuel by natural gas.

OWNERS: William T. Hinton
PRESIDENT

CERTIFICATE OF RESERVATION OF SANITARY SEWER AND DRAINAGE EASEMENTS

An easement for sanitary sewer and drainage purposes is hereby reserved on, over and under the areas of land and lakes as defined and bounded by dashed lines, marked "Sanitary Sewer and Drain Easement", together with the right of ingress and egress over all lots to and from the easements, for construction, reconstruction and maintenance of sewers and drains over said land. No permanent structure of any kind is to be erected on, over or under the land which is granted as said easements. The easements shall be for the benefit of the land in the subdivision and other land which becomes tributary thereto, and said sewers and drains may be constructed by the Louisville and Jefferson County Metropolitan Sewer District, or any other public sewers hereafter to be subject to approval of the Louisville and Jefferson County Metropolitan Sewer District.

OWNERS: William T. Hinton
PRESIDENT

CERTIFICATE OF RESERVATION OF GAS EASEMENT

The spaces outlined in dashed lines and marked "Gas Easement" are hereby reserved as easements for underground gas lines and appurtenances thereto, including the right to construct, operate, maintain, repair and remove such underground gas lines and appurtenances, and the right of ingress and egress over all lots to and from the easements and the right to cut down any trees within the easement that may interfere with the installation or operation of the lines. No permanent structure shall be erected within the easement. Any gas utility whose sole easement is within said permanent structure or obstruction within the easements. Fences, shrubbery and garages may occupy easement area at the property owner's risk.

(A) All property owners per entire supply lines shall be at the points designated by Louisville Gas and Electric Company (then L.G.&E.'s construction point throughout length of service and house lines and through customer's building), and title thereto shall remain in, and the cost of installation and maintenance thereof shall be borne individually by the respective lot owner upon which the said gas line serves.

Appropriate easements are hereby dedicated and reserved as such property owner, together with the right of ingress and egress over abutting lots or properties as needed, operate said pipelines, to lines of L.G.&E.'s installation points. Collars, in addition, shall require the cost because of said easements.

OWNERS: William T. Hinton
PRESIDENT

CERTIFICATE OF RESERVATION OF DRAINAGE RETENTION BASIN EASEMENT

Easements for drainage retention basin purposes are hereby reserved on, over the land and lakes as defined and bounded by dashed lines, marked "Drainage Retention Basin Easement", together with the right of ingress and egress over all lots to and from the easements, for construction, reconstruction of said basin and all appurtenances thereto, and the right to cut down or trim any trees within said easements, except for drainage structures, easements and landscape planting. The easements shall be for the benefit of the land in the subdivision and additional drainage improvements shall be constructed by Louisville and Jefferson County Metropolitan Sewer District, Jefferson County, or by any other public agency hereafter with jurisdiction for such improvements, or by others pursuant to agreement of the aforesaid sewer district or Jefferson County Works Department. Until such easements areas are accepted for the improvements by said Sewer District, Jefferson County, or another to dedicated public agency, said areas shall be maintained by the undersigned per owners lot.

OWNERS: William T. Hinton
PRESIDENT

PROPERTY OWNER'S OBLIGATION

Certain improvements in this subdivision are required by the Metropolitan Subdivision Regulations as specified by an approved construction plan on file in the office of the Director of Works. It is the obligation of every property owner in the subdivision not to obstruct, alter or destroy these improvements and not to allow any other person or agency to do so. Failure to comply with this requirement may result in the property owner being subject to the penalties set forth in the Metropolitan Subdivision Regulations.

NOTICE OF BOND REQUIREMENT

After construction acceptance and release of the above-named subdivision's bond by the Louisville and Jefferson County Planning Commission, the owner of any lot may be required to post a cash bond in the amount of $100.00 as a condition of obtaining a building permit pursuant to Section 3.7B of the Metropolitan Subdivision Regulations.

Donald A. Russell 1134 1/31/90
Signature PLS # Date

NOTES:

1) THERE SHALL BE NO FURTHER SUBDIVISION OR RESUBDIVISION OF THE LAND INTO A GREATER NUMBER OF LOTS THAN ORIGINALLY APPROVED.

2) THIS PLAT IS SUBJECT TO DEED OF RESTRICTION AS RECORDED IN DEED BOOK 5943 PAGE 0119

3) ALL ISLANDS, COMMON AREAS AND/OR RECREATION AREAS SHALL BE MAINTAINED BY HFH INC. OR BY NEIGHBORHOOD ASSOCIATION.

4) ALL NECESSARY RIGHTS FOR SANITARY SEWER & DRAINAGE PURPOSES ARE HEREBY RESERVED THROUGH AREAS MARKED "OPEN SPACE".

5) NO OPENINGS SHALL BE BELOW THE ELEVATIONS LISTED FOR THE FOLLOWING LOTS:

LOT #	MIN. OPENING EL.
249 - 252	660.6
253 - 257	663.7
270 - 274	644.9
291	642.5
315	649.0
322 - 325	640.6

THE DEPTH OF ALL ROADSIDE SWALES INCLUDING DRIVEWAY ENTRANCES AND CULVERTS UNDER DRIVEWAYS SHALL BE * INCHES BELOW FINISHED STREET CENTERLINE ELEVATIONS UNLESS OTHERWISE NOTED.

* NOT APPLICABLE SINCE ALL STREETS ARE CURB & GUTTER.

CERTIFICATE OF RESERVATION OF WATER LINE EASEMENT

Perpetual easements for water mains and appurtenances are hereby reserved on, over, under and through the strips of land as delineated and bounded by dashed lines marked "Louisville Water Company Easement", together with the right of ingress and egress over all lots to and from the easements for construction, operation, repairing, removing, relocating, inspecting, reconstructing, maintaining and inspecting of water mains. No permanent structures of any kind shall be erected on the strips of the land reserved for the use of the aforesaid water line easements without written consent of Louisville Water Company. Fences, shrubbery and similar non-structural accessories may be erected by the owner's risk. Temporary rights are hereby granted to use land adjacent to the permanent easements herein granted for ingress and egress of equipment, tools, materials, soils, and equipment during construction of said water lines.

William T. Hinton
PRESIDENT
OWNERS

LAND SURVEYOR'S CERTIFICATE

I hereby certify that this plat and survey were made under my supervision, and that the original and boundary monuments as indicated are substantially correct herein, are true and correct to the best of my knowledge and belief. That survey and plat meets or exceeds the minimum standards of surveying Kentucky.

STATE OF KENTUCKY
DONALD A. RUSSELL
1134
REGISTERED LAND SURVEYOR

#24248
3-14-91

LOCATION MAP



CENTERLINE CURVE DATA

7	6
R = 461.15'	R = 180.00'
Δ = 52°01'15"	Δ = 105°07'00"
A = 418.70'	A = 348.15'
T = 225.03'	T = 247.61'

—o— IRON PIN

UNLESS OTHERWISE SPECIFIED ALL RIGHT OF WAY INTERSECTION RADII SHALL BE 15'.

ALL CUL-DE-SAC RADII SHALL BE 50'.

NOTE:
POSITIVE DRAINAGE THROUGH AND AROUND THE GOLF COURSE SHALL BE MAINTAINED BY THIS GOLF COURSE OWNERS USING A SERIES OF SWALES SO AS TO PREVENT CONCENTRATIONS OF WATER FROM FLOWING ACROSS OR ONTO ADJACENT LOTS OR ROADWAYS. (A) THRU (C) DENOTES GOLF COURSE.

	Residential Area	31.6083 Acres
(A)	Recreation Area	10.7412 Acres
(B)	Recreation Area	27.1513 Acres
(C)	Recreation Area	45.9234 Acres
	Open Space	2.7235 Acres
	Total Area	118.1477 Acres


RECREATION AREA
H.F.H. INC. D.B. 5837 Pg. 661
GLENMARY DRIVE 60' R/W
GLEN FALLS COURT 50' R/W
GLENMARY FARM
GLENMARY FUTURE SECTION
MATCHLINE "C" SEE SHEET - 2
MATCHLINE "C" SEE SHEET - 2
30' SEWER & DRAIN. ESMT.
N 76°16'18"E 208.57
N 81°24'34"E 148.34
S 13°43'46"E 14.17
S 04°42'22"W 31.62
S 08°50'34"E 46.46
S 52°45'47"E 30.00
S 82°29'19"E 20.43
N 62°08'36"E 40.00
N 14°39'16"E 40.00
N 29°35'41"W 35.84
N 32°09'49"W 31.62
N 13°43'44"W 17.69
S 23°22'56"E 6.03
15' SEWER & DRAIN. ESMT.
N 52°30'34"W 377.03
N 37°29'26"E 337.83
N 37°08'17"E 330.83
N 37°08'17"E 330.83
N 02°05'51"E 328.30
N 71°05'51"E 228.53
N 71°05'51"E 228.53
N 02°05'51"E 328.30
N 37°08'17"E 330.83
N 37°08'17"E 330.83
N 42°29'26"E 384.26
N 42°29'26"E 184.16
30.00