

RIGHT OF WAY PLANS

DITCH CONSTRUCTION NOTES									
STATION RANGE	TYPE	BOTTOM WIDTH (FT.)	MATERIAL			MATERIAL			
			CHANNEL LINING			BLANKET			
			CLASS	D (FT.)	T (FT.)	QNT (TONS)	TYPE	D (FT.)	QNT (S.Y.)
511+00 TO 513+40	RT	SPECIAL					TRM 1	2.0	424
513+40 TO 517+00	RT	SPECIAL					ECB	2.0	634

PI STA. 514+00.99
 $\Delta = 4^{\circ}53'32''$ RT
 $T = 159.34'$
 $L = 318.49'$
 $M = 3730.00'$
 $e = 3.40'$
 $\theta = NC$
 Runoff = N/A
 Runout = N/A



ALL UTILITIES, UNLESS OTHERWISE NOTED, ARE CONSIDERED "OL C" PER KYTC DESIGN MANUAL SECTION HD-303.



COOPER CHAPEL ROAD SECTION III
 PLAN SHEET - MAINLINE
 STA. 511+00 TO STA. 517+00

FILE NAME: C:\PWORKING\PI\TT\DOB13532\34966-R5.DGN

USER: AMILES
DATE PLOTTED: November 19, 2020

E-SHEET NAME: R00500PL

MicroStation v8.11.9.919



RT. - STA. 48+60 TO STA. 49+04
CONSTRUCT 29 L.F. OF
STD. 2" ROLL CURB

RT. - STA. 49+04 TO STA. 48+89
TRANSITION FROM
STD. CURB & GUTTER
TO STD. 2" ROLL CURB
(15 L.F.)

LT. - STA. 517+00 - MAINLINE TO STA. 49+04 - MOUNTAIN LAUREL LANE
CONSTRUCT 139 L.F. OF
STD. CURB & GUTTER

LT. - STA. 517+00 - MAINLINE TO STA. 48+84 - MOUNTAIN LAUREL LANE
CONSTRUCT 89 S.Y. OF
CONCRETE SIDEWALK INCLUDING
1 TYPE 3 RAMP WITH DETECTABLE
WARNINGS

END CONSTRUCTION
STA. 48+85.75

LT. - STA. 48+60 TO STA. 49+04
CONSTRUCT 25 L.F. STD. 2" ROLL CURB

LT. - STA. 49+04 TO STA. 48+85
TRANSITION FROM STD. CURB & GUTTER TO
STD. 2" ROLL CURB (19 L.F.)

STA. 48+84 - MOUNTAIN LAUREL LANE TO
LT. - STA. 523+00 - MAINLINE
CONSTRUCT 298 S.Y. OF
CONCRETE SIDEWALK INCLUDING
1 TYPE 3 RAMP WITH DETECTABLE
WARNINGS

STA. 49+04 - MOUNTAIN LAUREL LANE TO
LT. - STA. 523+00 - MAINLINE
CONSTRUCT 520 L.F. OF
STD. CURB & GUTTER

STA. 518+09.86 MAINLINE =
STA. 50+00.00 MOUNTAIN LAUREL LANE =

FILE NAME: C:\PWORKING\PI\TT\0813532\34966-R7.DGN
USER: AMILES
DATE PLOTTED: February 1, 2021

E-SHEET NAME: R00700PL
MicroStation v8.11.9.919

RT. - STA. 517+00 TO STA. 517+97
CONSTRUCT 124 L.F. OF
STD. CURB & GUTTER

LT. - STA. 517+00 TO STA. 517+36
CONSTRUCT 11 S.Y. OF
4" COLORED CONCRETE

LT. - STA. 517+00 TO STA. 517+37
CONSTRUCT 75 L.F. OF
STD. CURB & GUTTER ALONG MEDIAN

END CONSTRUCTION
STA. 51+73.80

LT. - STA. 518+80 TO STA. 523+00
CONSTRUCT 460 S.Y. OF
4" COLORED CONCRETE

LT. - STA. 518+79 TO STA. 523+00
CONSTRUCT 848 L.F. OF
STD. CURB & GUTTER ALONG MEDIAN

DITCH CONSTRUCTION NOTES									
STATION RANGE	TYPE	BOTTOM WIDTH (FT.)	MATERIAL						
			CHANNEL LINING		BLANKET				
			CLASS	D (FT.)	T (FT.)	ONT (TONS)	TYPE	D (FT.)	ONT (S.Y.)
517+00 TO 517+75	RT	2.0					ECB	2.0	133
519+46 TO 520+90	RT	2.0					TRM 1	2.0	275
521+00 TO 522+00	LT	2.0					ECB	2.0	180
521+38 TO 523+00	RT	2.0					TRM 1	2.0	303
522+00 TO 523+00	LT	2.0					ECB	2.0	180

ALL UTILITIES, UNLESS OTHERWISE NOTED, ARE CONSIDERED "OL C" PER KYTC DESIGN MANUAL SECTION HD-303.

RIGHT OF WAY PLANS

COOPER CHAPEL ROAD SECTION III
PLAN SHEET - MAINLINE
STA. 517+00 TO STA. 523+00

