



MAXIMUM PARKING

6 SPACES (1 SP/500 SF) 28 SPACES (1 SP/100 SF)

15 SPACES (1 SP/500 SF)

\_ 3 SPACES

47,480 SF (1.09 Ac.)

14,244 SF (30%)

14,244 SF (30%)

2,281 SF

1 SPACES (1 SP/500 SF) 55 SPACES (1 SP/100 SF)

1.09 ACRES

RESTAURANT

REGIONAL CENTER

LOCATION MAP

NOT TO SCALE

## MSD NOTES

- 1) WASTEWATER: SANITARY SEWER SERVICE WILL BE PROVIDED BY NEW L.E. SANITARY SEWER FLOW WILL BE TREATED AT THE CEDAR CREEK WATER QUALITY
- 2) DRAINAGE: DRAINAGE PATTERN DEPICTED BY ARROWS (->) IS FOR CONCEPT PURPOSES ONLY. FINAL CONFIGURATION AND SIZE OF DRAINAGE PIPES, CHANNELS AND WATER QUALITY METHODS SHALL BE DETERMINED DURING THE CONSTRUCTION PLAN DESIGN PROCESS. DRAINAGE FACILITIES SHALL CONFORM TO MSD REQUIREMENTS. USE OF EX. DRAINAGE CONNECTIONS & STORM WATER REQUIREMENTS SHALL BE COORDINATED WITH MSD.
- 3) NO PORTION OF THE SUBJECT PROPERTY LIES WITHIN A FLOOD HAZARD AREA PER FEMA'S FIRM MAPPING, (21111C0097E REV. DECEMBER 5, 2006). 4) AN EPSC PLAN WILL BE SUBMITTED TO MSD FOR APPROVAL PRIOR TO ANY
- CONSTRUCTION ACTIVITY 5) THE FINAL DESIGN OF THIS PROJECT MUST MEET ALL MS4 WATER QUALITY
- REGULATIONS ESTABLISHED BY MSD. SITE LAYOUT MAY CHANGE AT THE CONSTRUCTION DESIGN PHASE DUE TO PROPERLY SIZING OF GREEN BEST MANAGEMENT PRACTICES
- 6) ALL RESTAURANTS MUST HAVE INDIVIDUAL CONNECTIONS PER MSD'S FATS, OIL AND GREASE POLICY.

## EROSION CONTROL NOTES

- 1) THE APPROVED EROSION PREVENTION AND SEDIMENT CONTROL (EPSC) PLAN SHALL BE IMPLEMENTED PRIOR TO ANY LAND DISTURBING ACTIVITY ON THE CONSTRUCTION SITE. ANY MODIFICATIONS TO THE APPROVED SWPP PLAN MUST BE REVIEWED AND APPROVED BY MSD'S PRIVATE DEVELOPMENT REVIEW OFFICE. SWPPP BMP'S SHALL BE INSTALLED PER THE PLAN AND MSD STANDARDS. 2) ACTIONS MUST BE TAKEN TO MINIMIZE THE TRACKING OF MUD AND SOIL FROM CONSTRUCTION AREAS ONTO PUBLIC ROADWAYS. SOIL TRACKED ONTO THE
- ROADWAY SHALL BE REMOVED DAILY.
- 3) SOIL STOCKPILES SHALL BE LOCATED AWAY FROM STREAMS, PONDS, SWALES, AND CATCH BASINS. SOIL STOCKPILES SHALL BE SEEDED, MULCHED, AND
- ADEQUATELY CONTAINED THROUGH USE OF SILT FENCE.
- 4) WHERE CONSTRUCTION OR LAND DISTURBANCE ACTIVITY WILL OR HAS TEMPORARILY CEASED ON ANY PORTION OF A SITE, TEMPORARY SITE STABILIZATION MEASURES SHALL BE REQUIRED AS SOON AS PRACTICABLE, BUT
- NO LATER THAN 14 CALENDAR DAYS AFTER THE ACTIVITY HAS CEASED. SEDIMENT LADEN GROUND WATER ENCOUNTERED DURING THE TRENCHING, BORING, OR OTHER EXCAVATION ACTIVITIES SHALL BE PUMPED TO A SEDIMENT TRAPPING DEVICE PRIOR TO BEING DISCHARGED INTO A STREAM, POND, SWALE,

CASE# 22-DDP-0105 WM# 9757

RELATED CASES# 21-DDP-0089, 19-DDP-0078, 17DEVPLAN1155 & 11640

JOB NO:

HORIZ. SCALE:

VERT SCALE:

DESIGNED BY:

DETAILED BY:

CHECKED BY:

DATE: SEPTEMBER 9, 2022

1"=20'