## **GENERAL NOTES:** 1) MSD WATER MANAGEMENT #10107. 2) ALL WORK PERFORMED ON THIS PROJECT SHALL CONFORM TO THE KENTUCKY TRANSPORTATION CABINET'S "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION," LATEST EDITION, UNLESS OTHERWISE SPECIFIED. 3) IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN ALL FEDERAL, STATE AND LOCAL PERMITS NECCESSARY TO PERFORM AND COMPLETE THE PROJECT AS SHOWN ON THESE PLANS. CONSTRUCTION STAKING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. ADDITIONAL INFORMATION STAKING THE PROJECT'S LINES AND GRADES AS SHOWN ON THESE PLANS WILL BE PROVIDED UPON REQUEST. 4) IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE ALL CONSTRUCTION ACTIVITIES WITH THE UTILITY COMPANIES SUCH THAT ACCESS TO WORK AREAS OR SCHEDULE CONFLICTS DO NOT INTERRUPT OR DELAY THE PROJECT'S SCHEDULE. 5) THE HORIZONTAL AND VERTICAL LOCATIONS OF EXISTING UTILITIES SHOWN ARE APPROXIMATE. IT SHALL BE THE RESPONSIBLITY OF THE CONTRACTOR TO LOCATE AND VERIFY ALL UTILITIES PRIOR TO BEGINNING CONSTRUCTION AND TO COORDINATE ALL CONNECTIONS WITH UTILITY 6) ALL STORM SEWER PIPE SHALL BE A MINIMUM OF 12" DIAMETER. 7) ALL CULVERTS UNDER PAVING HAVING LESS THAN 12" COVER SHALL BE CONCRETE ENCASED. 8) RING ALL CATCH BASINS WITH STONE BAGS DURING GRADING OPERATIONS.

SEWER DISTRICT'S STANDARD SPECIFICATIONS.

AND PONDING AREAS WILL NOT BE ACCEPTABLE.

PÉRVIOUS AREAS ON THE PROJECT.

21) NO NEW SANITARY FACILITIES.

AGENCIES REQUIRE OTHERWISE.

WITH LDC CHAPTER 10.

NEIGHBORING PROPERTIES.

COUNTY METRO ORDINANCES.

PER THE PLAN AND MSD STANDARDS.

AFTER THE ACTIVITY HAS CEASED.

ONTO THE ROADWAY SHALL BE REMOVED DAILY.

CROSSING STRUCTURES PER MSD STANDARD DRAWING ER-02.

BFING DISCHARGE INTO A STREAM, POND, SWALE OR CATCH BASIN.

21111C0024E)

SHOWN OTHERWISE. ALL RADAII SHOWN ARE ON FACE OF CURB.

BINDER INSTALLATION.

TO 100%. MOISTURE CONTENT SHALL BE WITHIN +3% TO -1% OF OPTIMUM.

AT 25' INTERVALS, AT ALL BENDS AND WHERE ABUTTING RIGID STRUCTURES.

RÉGULATIONS 28 CFR PART 36: ADA STANDARDS FOR ACCESSIBLE DESIGN.

25) ALL SIGNAGE SHALL COMPLY WITH LDC CHAPTER 8, SIGN REGULATIONS.

DETENTION BASINS, IF APPLICABLE, SHALL BE CONSTRUCTED FIRST AND SHALL PERFORM

AS SEDIMENT BASINS DURING CONSTRUCTION UNTIL THE CONTRIBUTING DRAINAGE AREAS ARE SEEDED AND STABILIZED. ACTIONS MUST BE TAKEN TO MINIMIZE THE TRACKING OF

MUD AND SOIL FROM CONSTRUCTION AREAS ONTO PUBLIC ROADWAYS. SOILS TRACKED

SOIL STOCKPILES SHALL BE LOCATED AWAY FROM STREAMS, PONDS, SWALES, AND CATCH

THROUGH THE USE OF SILT FENCING. ALL STREAM CROSSINGS MUST UTILIZE LOW-WATER

BASINS. STOCKPILES SHALL BE SEEDED, MULCHED, AND ADEQUATELY CONTAINED

WHERE CONSTRUCTION OR LAND DISTURBANCE ACTIVITY WILL OR HAS TEMPORARILY

CEASED ON ANY PORTION OF A SITE, TEMPORARY SITE STABILIZATION MEASURES SHALL


SEDIMENT-LADEN GROUNDWATER ENCOUNTERED DURING TRENCHING, BORING OR OTHER


EXCAVATION ACTIVITIES SHALL BE PUMPED TO A SEDIMENT TRAPPING DEVICE PRIOR TO


BE REQUIRED AS SOON AS PRACTICABLE, BUT NO LATER THAN 14 CALENDAR DAYS


22) DRAINAGE FACILITIES SHALL CONFORM TO MSD REQUIREMENTS.


DOWN AND AWAY FROM ANY RESIDENTIAL PROPERTIES.

















AREA OF DISTURBANCE IS LESS THAN 1 ACRE.

MSD'S MS4 REGULATIONS DO NOT APPLY.

GRAPHIC SCALE: 1"= 40'

BLOMQUIST DESIGN GROUP, LLC

10529 TIMBERWOOD CIRCLE SUITE "D"

LOUISVILLE, KENTUCKY 40223

EMAIL: MARVBDG@AOL.COM

160 PHONE: 502.429.0105 FAX: 502.429.6861

BUILDING HEIGHT ... 25 FT. MAX. 0.114 72 MIN. (1 PER 50 S.F. SANCTUARY SEATING: REQUIRED PARKING... 1 PER 500 S.F. RETAIL) 24° COMBINED SEWER RECORD - 10% TARC CREDIT NO. USI3-3 113 MAX. (125% OF MINIMUM SANCTUARY; 1 PER 250 S.F. RETAIL) -PROPOSED 5 78, INCL. 4 ADA PROVIDED PARKING.. PROVIDED BICYCLE PARKING...... 4 SHORT-TERM PARKING & 2 LONG-TERM PARKING SIDEWALK 41,195 S.F. PROPOSED VUA.. 2,060 S.F. (5.0%) REQUIRED ILA. .. 3,498 S.F. (8.5%) 216 L.F. SILT FENCE PROVIDED ILA.... MSD STD EF-09-02 EXISTING TREE CANOPY... REQUIRED TREE CANOPY.... . 15**% (**16,597 S.F.) PROPOSED MONUMENT SIGN (2 TENANTS) INCREASE IN IMPERVIOUS AREA 8 FT. MAX HIGH 72 SQ. FT. MAX 📥 PREDEVELOPED IMPERVIOUS AREA = 110,643 SQ. FT. NO. USI3-3 DEVELOPED IMPERVIOUS AREA = 86,261 SQ. FT. INCREASE IN IMPERVIOUS AREA = (-24,382 SQ. FT.)Brate EL 453.9 invert EL 453.0 LEGEND 1/2 " DIAMETER STEEL REINFORCING BAR WITH ORANGE PLASTIC CAP STAMPED "WI 2852" SET EXISTING POLE PARKER-KALON NAIL WITH BRASS WASHER TELEPHONE POLE STAMPED "2852", SET PREVIOUS SURVEY POLE ANCHOR LIGHT POLE TREE/SHRUB SANITARY/STORM MANHOLE **FENCE** MONITORING WELL POWER POLE WATER METER FIRE HYDRANT GRAVITY SANITARY SEWER LINE / STORM SEWER BURIED TELEPHONE/FIBER OPTIC WATER LINE OVERHEAD UTILITY LINE PHYSICALLY CHALLENGED PARKING SPACE INTERIOR PROPERTY LINE CLEAN OUT CURB BOX INLET 00 CHAIN LINK FENCE DROP BOX INLET TEMPORARY BENCHMARK GAS METER WATER METER EXISTING PLANTING ----- EXISTING CONTOUR TREE PROTECTION FENCE MARV A. EXISTING DRAINAGE ARROW BLOMQUIS 14.890 PROPOSED DRAINAGE ARROW PROPOSED PLANTING PORTLAND PRESBYTERIAN CHURCHIVED 3126 PORTLAND AVENUE OCT 16 2015 TAX BLOCK 10B, LOT 87: FULLIALING 8 DB 9587, PG 334 DESIGN SERVICE FORM DISTRICT: TRADITIONAL NEIGHBORHOOD ZONE: C-2 REVISIONS SCALE: OWNER/DEVELOPER: 1"= 40" PORTLAND AVENUE PRESBYTERIAN CHURCH DRWN: KLW 3126 PORTLAND AVENUE C-1LOUISVILLE, KY 40212 CKD: MAB DATE: 1 SDEV PLANT OCTOBER 16, 2015 WM #10107

DEVELOPMENT

EXISTING ZONE ...

EXISTING USE...

PROPOSED USE...

PROPERTY AREA..

EXISTING FORM DISTRICT...

EXISTING BUILDING S.F. .....

INTERSTATE 64

VICINITY MAP

.. C-2

TRADITIONAL NEIGHBORHOOD

2.54 ACRES (110,643 S.F.)

EXISTING RETAIL 9,600 S.F.

. CHURCH/ MERCANTILE- THRIFT STORE

CHURCH/ MERCANTILE- THRIFT STORE

EXISTING SANCTUARY SEATING AREA 3,000 S.F.

SITE DATA CHART

Jones VI