

LEGEND
EXISTING CONTOUR
EXISTING SPOT ELEVATION
SINKHOLE
EXISTING TREE MASS
EXISTING FENCE
EXISTING GUARDRAIL
EXISTING WATER LINE W/SIZE
EXISTING WATER METER
EXISTING WATER VALVE
EXISTING FIRE HYDRANT
EXISTING GAS W/ SIZE
EXISTING OVERHEAD UTILITIES
EXISTING UTILITY POLE
EXISTING DOWN GUY
EXISTING ELECTRIC BOX
EXISTING LIGHT POLE BASE
EXISTING CATCH BASIN W/ PIPE
EXISTING HEADWALL W/ PIPE
EXISTING SANITARY MANHOLE W/PIPE
EXISTING 4\"/>

SITE DATA:
FORM DISTRICT
EXISTING ZONING
R-4
R-6
R-7
EXISTING LAND USE
PROPOSED LAND USE
GROSS LAND AREA
NET LAND AREA
NO. OF DWELLING UNITS
BUILDING HEIGHT
(MAX. ALLOWED R6 35')
(MAX. ALLOWED R7 45')
R6 DENSITY (MAX. ALLOWED 17.42)
F.A.R. ALLOWED
F.A.R. PROPOSED
R7 DENSITY (MAX. ALLOWED 34.80)
F.A.R. ALLOWED
F.A.R. PROPOSED
OPEN SPACE REQUIRED
OPEN SPACE PROVIDED
REC. OPEN SPACE REQUIRED
REC. OPEN SPACE PROVIDED
PARKING REQUIRED
MIN. 1.5 SPACES/D.U.
MAX. 3 SPACES/D.U.
PARKING PROVIDED
50 GARAGE SPACES
41 A.D.A. SPACES (1 IN GARAGE)
959 SURFACE SPACES

NEIGHBORHOOD
0.53± AC.
18.56± AC.
29.12± AC.
AGRICULTURAL
MULTI-FAMILY RESIDENTIAL
44.68± AC.
496
35'
9.26 D.U./AC.
0.75
0.12
11.13 D.U./AC.
1.00
0.18
291,939 S.F. (15%)
319,065± S.F.
145,970 S.F. (7.5%)
176,235± S.F.
744 SPACES
1,488 SPACES
1,037 SPACES
1,049 TOTAL

LANDSCAPE DATA:
V.U.A. 372,923± S.F.
I.L.A. REQUIRED (7.5% x V.U.A.) 27,969± S.F.
I.L.A. PROVIDED 36,306± S.F.

NEIGHBORHOOD
R4, R6 & R7
R4, R6 & R7
VACANT AGRICULTURAL
MULTI-FAMILY RESIDENTIAL
48.21 AC. / 2,100,028± S.F.
CLASS C
649,833± S.F. (31%)
255,160± S.F.
5,972± S.F.
261,133± S.F. (12.4%)
336,005± S.F. (16%)
2,160± S.F.
106± S.F.
263,399± S.F. (12.5%)
72,606± S.F.
336,005± S.F. (16%)

DETENTION CALCULATIONS:
2.9/12 (0.58 - 0.30)/(48.21) = 3.26 AC-FT
POST-DEVELOPED C FACTOR BASED ON 20.78 AC. OF IMPERVIOUS SURFACES AND 27.43 AC. OF OPEN SPACE/UNDISTURBED AREAS.
DETENTION VOLUME PROVIDED = 6.48 AC-FT
• DETENTION BASIN #1 IS 13.75 FEET DEEP WITH A VOLUME OF 3.34 AC-FT
• DETENTION BASIN #2 IS 7 FEET DEEP WITH A VOLUME OF 3.14 AC-FT

GENERAL NOTES:
1. DOMESTIC WATER SUPPLY: SUBJECT SITE CAN BE SERVED BY THE LOUISVILLE WATER COMPANY. THE NECESSARY WATER SYSTEM IMPROVEMENTS REQUIRED TO SERVICE THE DEVELOPMENT SHALL BE AT THE OWNER/DEVELOPER'S EXPENSE.
2. TREE PRESERVATION: A TREE PRESERVATION PLAN SHALL BE PROVIDED TO THE PLANNING COMMISSION'S STAFF LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITIES ON THE SITE.
3. PROTECTION OF TREES TO BE PRESERVED: CONSTRUCTION FENCING SHALL BE ERECTED PRIOR TO ANY GRADING OR CONSTRUCTION ACTIVITIES PREVENTING COMPACTION OF ROOT SYSTEMS OF TREES TO BE PRESERVED. THE FENCING SHALL ENCLOSE THE AREA BENEATH THE DRIP LINE OF THE TREE CANOPY AND SHALL REMAIN IN PLACE UNTIL ALL CONSTRUCTION IS COMPLETE. NO PARKING, MATERIAL STORAGE OR CONSTRUCTION ACTIVITIES SHALL BE PERMITTED WITHIN THE FENCED AREA.
4. A LANDSCAPE AND TREE CANOPY PLAN PER CHAPTER 10 OF THE LDC SHALL BE PROVIDED AS REQUIRED PRIOR TO ISSUANCE OF BUILDING PERMIT.
5. THE DEVELOPMENT LIES IN THE BUECHEL AND FERN CREEK FIRE DISTRICTS.
6. SIGNATURE ENTRANCE WALLS SHALL BE SUBMITTED TO AND APPROVED BY THE PLANNING STAFF PRIOR TO CONSTRUCTION PLAN APPROVAL AND THEY SHALL MEET THE REQUIREMENTS OF CHAPTER 4.3 OF THE LDC.
7. ALL LUMINAIRES SHALL BE AIMED, DIRECTED OR FOCUSED SUCH AS TO NOT CAUSE DIRECT LIGHT FROM THE LUMINAIRES TO BE DIRECTED TOWARDS RESIDENTIAL USES OR PROJECTED OPEN SPACES (IE. CONSERVATION EASEMENTS, GREENWAYS OR PARKWAYS) ON ADJACENT OR NEARBY PARCELS, OR TO CREATE GLARE PERCEPTIBLE ON PUBLIC STREETS AND RIGHT-OF-WAYS PER CHAPTER 4.1.3 OF THE LDC.
8. DOCUMENTATION SHALL BE REQUIRED PRIOR TO CONSTRUCTION APPROVAL SHOWING THAT THE DEVELOPMENT COMPLIES WITH ALL LIGHTING REGULATIONS FROM CHAPTER 4, PART 1, SECTION 3.
9. ALL DUMPSTER PADS, TRANSFORMERS, AC UNITS, GENERATOR PADS TO BE SCREENED PER CHAPTER 10 OF THE LDC.
10. BUILDING ARCHITECTURE TO COMPLY WITH CHAPTER 5.4 OF THE LDC.
11. ALL INTERIOR SIDEWALKS THAT ADJUT PARKING TO BE FIVE (5) FEET WIDE MINIMUM.
12. MITIGATION MEASURES FOR DUST CONTROL SHALL BE IN PLACE DURING CONSTRUCTION TO PREVENT FUGITIVE EMISSIONS REACHING EXISTING ROADS AND NEIGHBORHOODS.
13. ALL EXISTING STRUCTURES AND EXISTING ENTRANCES SHALL BE REMOVED, EXCEPT AS NOTED ON THE PLAN.
14. IN ACCORDANCE WITH CHAPTER 4.9 OF THE LDC, A KARST SURVEY WAS PERFORMED BY GEM ENGINEERING ON 1/3/2007 & 6/5/2007 AND KARST TOPOGRAPHY WAS FOUND. REFER TO GEM ENGINEERING GEO-TECHNICAL EXPLORATION REPORT, PROJECT NO. 6-1-07.
15. PARKWAY PLANTINGS MUST BE INSTALLED WITHIN 6 MONTHS OR NEXT AVAILABLE PLANTING SEASON PER PDS STAFF, FROM THE ISSUANCE OF THE SITE DISTURBANCE/CLEARING AND GRADING PERMIT.

MSD NOTES:


1. WASTEWATER: SANITARY SEWER WILL CONNECT TO THE DEREK GUTHRIE WASTEWATER TREATMENT PLANT BY LATERAL EXTENSION AGREEMENT, SUBJECT TO FEES. SANITARY SEWER CAPACITY TO BE APPROVED BY METROPOLITAN TREATMENT DISTRICT.
2. DRAINAGE/STORMWATER DETENTION: ON-SITE DETENTION WILL BE PROVIDED. POST-DEVELOPED PEAK FLOWS WILL BE LIMITED TO PRE-DEVELOPED PEAK FLOWS FOR THE 2, 10, 25, AND 100-YEAR STORMS OR TO THE CAPACITY OF THE DOWNSIDE SYSTEM, WHICHEVER IS MORE RESTRICTIVE. DRAINAGE PATTERN (DEPICTED BY FLOW ARROWS) IS FOR CONCEPT PURPOSES ONLY. FINAL CONFIGURATION AND SIZE OF DRAINAGE PIPES AND CHANNELS SHALL BE DETERMINED DURING THE CONSTRUCTION PLAN DESIGN PROCESS. DRAINAGE FACILITIES SHALL CONFORM TO MSD REQUIREMENTS.
3. SITE IS SUBJECT TO REGIONAL FACILITY FEE X 1.5 FOR INCREASED RUN-OFF VOLUME.
4. THE PROPOSED DRAINAGE AND STORM SEWERS SHOWN ON PLAN ARE CONCEPTUAL. FINAL DESIGN SHALL BE DETERMINED DURING THE CONSTRUCTION PLAN DESIGN PROCESS AND SHALL CONFORM TO MSD REQUIREMENTS.
5. A MSD DRAINAGE BOND WILL BE REQUIRED.
6. APPROVAL FROM THE CORPS OF ENGINEERS WILL BE REQUIRED FOR CONSTRUCTION OF THE BERM FOR BASIN #1 IF IT MEETS THE DAM HEIGHT LIMITS. REQUIREMENT OF THE DAM SAFETY LAW SHALL BE OBSERVED. APPROVAL FROM DESIGN OF WATER WILL BE REQUIRED.
7. EROSION AND SILT CONTROL: A SOIL AND SEDIMENTATION CONTROL PLAN SHALL BE DEVELOPED AND IMPLEMENTED IN ACCORDANCE WITH MSD AND THE USDA NATURAL RESOURCES CONSERVATION SERVICE RECOMMENDATIONS. DOCUMENTATION OF MSD'S APPROVAL OF THE PLAN SHALL BE SUBMITTED TO THE PLANNING COMMISSION PRIOR TO GRADING AND CONSTRUCTION ACTIVITIES.
8. A PORTION OF THE SUBJECT PROPERTY LIES WITHIN A FLOOD HAZARD AREA PER FEMA'S FIRM MAPPING (21111C0078E).
9. THE FINAL DESIGN OF THIS PROJECT MUST MEET ALL MSD WATER QUALITY REGULATIONS ESTABLISHED BY MSD. SITE LAYOUT MAY CHANGE AT DESIGN PHASE DUE TO PROPER SIZING OF GREEN BEST MANAGEMENT PRACTICES.
10. EASEMENT FOR THOROUGH DRAINAGE FOR DETENTION BASIN #2 TO BE GRANTED BY ADJACENT OWNER OF BLOCK 627 LOT 78 DURING DEVELOPMENT OF THAT PROPERTY.

BEARINGS & DISTANCES
① N 02°55'31\"/>

GRAPHIC SCALE 1"=100'
0 50 100 200

CASE # 17DEVPLAN1016
PREVIOUS CASE #13DEVPLAN1035
MSD WM # 9582

BUILDING TYPE (NO. OF UNITS)	BUILDING SIZE OVERALL SQ. FT.	BUILDING NUMBERS AS SHOWN ON SITE PLAN	NO. OF BUILDINGS OF THIS TYPE	NUMBER OF UNITS
1A (16)	9,630 SF	7, 19, 20, 21, 25, 28, 29, 33	8	128
1B (20)	9,630 SF	2, 12	2	40
2A (16)	11,590 SF	5, 6, 8, 18, 23, 26, 30, 31, 32, 34, 35	11	176
2B (20)	11,590 SF	11, 13, 14	3	60
2C (10)	5,495 SF	9, 10	2	20
2D (8)	6,127 SF	16, 22, 38	3	24
3 TH (4)	4,592 SF	1, 3, 4, 15, 24, 27, 36, 37	8	32
3A (16)	13,877 SF	17	1	16
1 THROUGH 38			38	496



**TYPICAL SECTION
ACCESS ROADWAY TO FEGBENBUSH**
NO SCALE
REFERENCED IN D.B. 9164 PG. 23 & D.B. 9012 PG. 17

Mindel, Scott & Associates, Inc.
Planning • Engineering • Surveying • Landscape Architecture
Utility Consulting • Property Management
Phone: (502) 485-1300 Fax: (502) 485-1300 E-Mail: info@msa-hd.com

MSA

OWNER/DEVELOPER
WILLOW GREEN, LTD.
122 NORTH PETERSON AVENUE
LOUISVILLE, KY 40206
(502) 895-1677

REVISED DISTRICT DEVELOPMENT PLAN
WILLOW GREEN
6005 FEGBENBUSH LN. & 7101 FERN RIDGE RD.
LOUISVILLE, KY 40218
TAX BLOCK: 627 LOTS: 73, 74, 75, 76
D.B. 10806 PG. 704

Revisions	3/13/17	5/05/17	5/18/17
PER AGENCY REVIEW			
PER AGENCY REVIEW			
PER AGENCY REVIEW			

Vertical Scale: N/A
Horizontal Scale: 1"=100'
Date: 1/30/17
Job Number: 3366-100
Sheet
1
of 1