GENERAL NOTES: 1) MSD WATER MANAGEMENT #11781. 3) IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN ALL FEDERAL, STATE AND LOCAL PERMITS NECESSARY TO PERFORM AND COMPLETE THE PROJECT AS SHOWN ON THESE PLANS. AND WELLNESS IN ACCORDANCE WITH CHAPTER 115 OF LOUISVILLE JEFFERSON COUNTY METRO ORDINANCES. 30) THE FINAL DESIGN OF THIS PROJECT MUST MEET ALL MS4 WATER QUALITY REGULATIONS ESTABLISHED 31) MINOR PLAT TO RECORD THE LOT TO BE RECORDED PRIOR TO DEVELOPMENT PLAN APPROVAL. 32) CONSTRUCTION PLANS AND DOCUMENTS SHALL COMPLY WITH LOUISVILLE AND JEFFERSON COUNTY METROPOLITAN SEWER DISTRICT'S DESIGN MANUAL AND STANDARD SPECIFICATIONS AND OTHER LOCAL, 33) SITE IS SUBJECT TO REGIONAL FACILITY FEE'S X 1.5. 34) IN ACCORDANCE WITH CHAPTER 4.9 OF THE LDC, A KARST SURVEY WAS PERFORMED BY MIKE ELLIS, ECS SOUTHEAST, LLP ON JUNE 22, 2018 AND NO KARST FEATURES WERE FOUND.

2) ALL WORK PERFORMED ON THIS PROJECT SHALL CONFORM TO THE KENTUCKY TRANSPORTATION CABINET'S "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION," LATEST EDITION, UNLESS OTHERWISE SPECIFIED. CONSTRUCTION STAKING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. ADDITIONAL INFORMATION STAKING THE PROJECT'S LINES AND GRADES AS SHOWN ON THESE PLANS WILL BE PROVIDED UPON REQUEST. 4) IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE ALL CONSTRUCTION ACTIVITIES WITH THE UTILITY COMPANIES SUCH THAT ACCESS TO WORK AREAS OR SCHEDULE CONFLICTS DO NOT INTERRUPT OR DELAY THE PROJECT'S SCHEDULE. 5) THE HORIZONTAL AND VERTICAL LOCATIONS OF EXISTING UTILITIES SHOWN ARE APPROXIMATE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE AND VERIFY ALL UTILITIES PRIOR TO BEGINNING CONSTRUCTION AND TO COORDINATE ALL CONNECTIONS WITH UTILITY COMPANIES. 6) ALL STORM SEWER PIPE SHALL BE A MINIMUM OF 12" DIAMETER. 7) ALL CULVERTS UNDER PAVING HAVING LESS THAN 12" COVER SHALL BE CONCRETE ENCASED. 8) RING ALL CATCH BASINS WITH STONE BAGS DURING GRADING OPERATIONS. 9) ALL STORM DRAIN CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE METROPOLITAN SEWER DISTRICT'S STANDARD SPECIFICATIONS. 10) DENSE-GRADED AGGREGATE BASE SHALL BE COMPACTED IN SEPARATE LAYERS. FOR ASPHALT PARKING LOTS, CONTRACTOR SHALL RECEIVE APPROVAL FOR JOB MIX FORMULA. 12) ALL SUBGRADES SHALL BE COMPACTED TO 95% OF MAXIMUM DENSITY AS DETERMINED BY THE STANDARD PROCTOR. THE UPPER 12" OF FILL BENEATH PAVEMENTS SHALL BE COMPACTED TO 100%. MOISTURE CONTENT SHALL BE WITHIN +3% TO -1% OF OPTIMUM. 13) TACK COAT SHALL BE APPLIED AT THE RATE OF 0.1 GALS. PER SQ. YARD WITH INSTALLATION OF SURFACE ASPHALT WHEN FINAL PAVING HAS BEEN DELAYED FROM THE BINDER INSTALLATION. 14) THE CONTRACTOR SHALL SLOPE ALL FINISH GRADES TO PROVIDE POSITIVE DRAINAGE. FLAT AND PONDING AREAS WILL NOT BE ACCEPTABLE. 15) THE MINIMUM GRADE OF ALL STREETS SHALL BE 1% AND MAXIMUM SHALL BE 10%. 16) DIMENSIONS SHOWN HEREON ARE FROM THE EDGE OF GUTTERS OR WALLS UNLESS SHOWN OTHERWISE. ALL RADAII SHOWN ARE ON FACE OF CURB. 17) SIDEWALKS SHALL BE A MINIMUM 5" THICK WITH 6" X 6" W.W.F. ON A 4" D.G.A. BASE. SIDEWALKS AT DRIVEWAYS SHALL HAVE A MINIMUM THICKNESS OF 6". A FINE BROOM FINISH SHALL BE PROVIDED WITH CONTROL JOINTS SPACED AT 5' INTERVALS AND EXPANSION JOINTS AT 25' INTERVALS, AT ALL BENDS AND WHERE ABUTTING RIGID STRUCTURES. 18) THE CONTRACTOR SHALL PROVIDE A COMPACTED DEPTH OF 6" TOPSOIL OVER ALL PERVIOUS AREAS ON THE PROJECT. 19) ALL HANDICAP SITE FEATURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH FEDERAL REGULATIONS 28 CFR PART 36: ADA STANDARDS FOR ACCESSIBLE DESIGN. 20) THIS PROPERTY IS NOT LOCATED IN A 100 YEAR FLOOD HAZARD AREA. (FEMA MAP 21111C0260 D) 21) SANITARY SEWERS ARE AVAILABLE BY EXISTING CONNECTION FROM THE EXISTING SEWER RECORD NUMBER 14301-2, SUBJECT TO FEES. 22) DRAINAGE FACILITIES SHALL CONFORM TO MSD REQUIREMENTS. 23) COMPATIBLE UTILITIES SHALL BE PLACE IN A COMMON TRENCH UNLESS APPLICABLE AGENCIES REQUIRE OTHERWISE. 24) SITE LIGHTING SHALL NOT SHINE IN THE EYES OF DRIVERS AND SHALL BE DIRECTED DOWN AND AWAY FROM ANY RESIDENTIAL PROPERTIES. 25) ALL SIGNAGE SHALL COMPLY WITH LDC CHAPTER 8, SIGN REGULATIONS. 26) ALL SERVICE STRUCTURES, INCLUDING DUMPSTER SHALL BE SCREENED IN ACCORDANCE WITH LDC 27) MITIGATION MEASURES FOR DUST CONTROL SHALL BE IN PLACE DURING CONSTRUCTION TO PREVENT FÚTIGIVE PARTICULATE EMISSIONS FROM REACHING EXISTING ROADS AND NEIGHBORING PROPERTIES.

28) ALL CONSTRUCTION AND SALES TRAILERS MUST BE PERMITTED BY THE DEPARTMENT OF PUBLIC HEALTH

29) CONSTRUCTION PLANS AND BOND ARE REQUIRED BY METRO PUBLIC WORKS PRIOR TO CONSTRUCTION APPROVAL AND ISSUANCE OF MPW ENCROACHMENT PERMIT.


BY MSD. SITE LAYOUT MAY CHANGE AT THE DESIGN PHASE DUE TO PROPER SIZING OF GREEN BEST MANAGEMENT PRACTICES.

STATE, AND FEDERAL ORDINANCES.

35) "NO PARKING/FIRE LANE" SIGNS TO BE INSTALLED ON BOTH SIDES OF SOUTHPOINT DRIVE.

UTILITY NOTE

ALL UTILITIES ON THESE PLANS ARE APPROXIMATE. INDIVIDUAL SERVICE LINES ARE NOT SHOWN. THE CONTRACTOR OR SUBCONTRACTOR SHALL NOTIFY THE UTILITY PROTECTION CENTER KENTUCKY 811 (TOLL FREE PHONE NO. 1-800-752-6007 OR LOCAL NO. 502-266-5123) FORTY-EIGHT (48) HOURS IN ADVANCE OF ANY CONSTRUCTION ON THIS PROJECT. THIS NUMBER WAS ESTABLISHED TO PROVIDE ACCURATE LOCATIONS OF EXISTING BELOW GROUND UTILITIES (I.E. CABLES, ELECTRIC WIRES, GAS & WATER LINES). WHEN CONTACTING THE KENTUCKY 811 CALL CENTER, PLEASE STATE THE WORK TO BE DONE IS FOR A PROPOSED MSD SEWER OR DRAINAGE FACILITY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR BECOMING FAMILIAR WITH ALL UTILITY REQUIREMENTS SET FORTH ON THE PLANS AND IN THE TECHNICAL SPECIFICATIONS & SPECIAL PROVISIONS.



BROOKLEY PLACE CONDOMINIUMS

APARTMENT OWNERSHIP BOOK 99, PAGES 36-38

EROSION PREVENTION and SEDIMENT CONTROL

THE APPROVED EROSION PREVENTION AND SEDIMENT CONTROL (EPSC) PLAN SHALL BE

ANY MODIFICATIONS TO THE APPROVED EPSC PLAN MUST BE REVIEWED AND APPROVED

DETENTION BASINS, IF APPLICABLE, SHALL BE CONSTRUCTED FIRST AND SHALL PERFORM AS SEDIMENT BASINS DURING CONSTRUCTION UNTIL THE CONTRIBUTING DRAINAGE AREAS

ARE SEEDED AND STABILIZED. ACTIONS MUST BE TAKEN TO MINIMIZE THE TRACKING OF MUD AND SOIL FROM CONSTRUCTION AREAS ONTO PUBLIC ROADWAYS. SOILS TRACKED

SOIL STOCKPILES SHALL BE LOCATED AWAY FROM STREAMS, PONDS, SWALES, AND CATCH

THROUGH THE USE OF SILT FENCING. ALL STREAM CROSSINGS MUST UTILIZE LOW-WATER

CEASED ON ANY PORTION OF A SITE. TEMPORARY SITE STABILIZATION MEASURES SHALL

SEDIMENT-LADEN GROUNDWATER ENCOUNTERED DURING TRENCHING, BORING OR OTHER

EXCAVATION ACTIVITIES SHALL BE PUMPED TO A SEDIMENT TRAPPING DEVICE PRIOR TO

BASINS. STOCKPILES SHALL BE SEEDED, MULCHED, AND ADEQUATELY CONTAINED

WHERE CONSTRUCTION OR LAND DISTURBANCE ACTIVITY WILL OR HAS TEMPORARILY

BE REQUIRED AS SOON AS PRACTICABLE, BUT NO LATER THAN 14 CALENDAR DAYS

IMPLEMENTED PRIOR TO ANY LAND-DISTURBING ACTIVITY ON THE CONSTRUCTION SITE.

BY MSD'S PRIVATE DEVELOPMENT REVIEW OFFICE. EPSC BMP'S SHALL BE INSTALLED

PER THE PLAN AND MSD STANDARDS.

AFTER THE ACTIVITY HAS CEASED.

ONTO THE ROADWAY SHALL BE REMOVED DAILY.

CROSSING STRUCTURES PER MSD STANDARD DRAWING ER-02.

BEING DISCHARGE INTO A STREAM, POND, SWALE OR CATCH BASIN.

ORKPLACE FORM DISTRICT

GRAPHIC SCALE: 1"= 50'

COOPER CHAPEL RD. MT. WASHINGTON RD.

MUD LANE

/ICINITY MAP NTS

DUISVILLE, JEFFERSON CO., KY

VICINITY MAP

N.T.S.

1-265 GENE SNYDER PARKWA.


SITE DATA CHART

EXISTING ZONE	SUBURBAN WORKPLACE RESIDENTIAL MULTI-FAMILY VACANT SENIOR HOUSING 5.525 ACRES (240,656.3 S.F.) 120 DWELLING UNITS 21.72 DWELLING UNITS PER ACRE 34.8 DWELLING UNITS PER ACRE 45 FT. MAX. (FOUR STORIES) 0.584 62 MIN. (.5 PER UNIT, 1 PER 2 EMPLOYEES) 183 MAX. (1.5 PER UNIT, 1 PER EMPLOYEE) 116, INCL. 6 ADA & 40 GARAGES 60,855 S.F. 4,566 S.F. (7.5%) 7,669 SF. (12.6%) 100%
EXISTING TREE CANOPY	100% 14.5% (35,000 S.F.)

INCREASE IN IMPERVIOUS AREA

PREDEVELOPED IMPERVIOUS AREA = 0 SQ. FT.DEVELOPED IMPERVIOUS AREA = 104,161 SQ. FT. INCREASE IN IMPERVIOUS AREA = 104,161 SQ. FT.

LEGEND





PROPERTY DEED BOOK 10558 PAGE 723

PARCEL ID: 0090-0117-0000

ZONED R-7

SUBURBAN WORKPLACE FORM DISTRIC',

BLOMQUIST DESIGN GROUP, LLC 10529 TIMBERWOOD CIRCLE SUITE "D"

LOUISVILLE, KENTUCKY 40223 200 PHONE: 502.429.0105 FAX: 502.429.6861 EMAIL: MARVBDG@AOL.COM


REVISIONS SCALE: 1"= 50' DRWN: KLW SEPT 12, 2018

DETAILED DISTRICT DEVELOPMENT PLAN

SOUTHPOINT

ZONED PEC, SUBURBAN WORKPLACE FORM DISTRICT 11700 INTERCHANGE DRIVE LOUISVILLE, KY 40229 TAX BLOCK 3514, LOT 0002 DEED BOOK 9042, PAGE 30

OWNER/ DEVELOPER: GAULT-MARSH PROPERTIES SOUTHPOINT, LLC. 4011 GARDINER POINT DRIVE, SUITE 200 LOUISVILLE. KY 40213-1988



14,890