UTILITIES NOTE

ALL UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE. INDIVIDUAL SERVICE LINES ARE NOT SHOWN. THE CONTRACTOR OR SUBCONTRACTOR SHALL NOTIFY THE UTILITY PROTECTION CENTER, "KENTUCKY 811" (TOLL FREE PHONE NO. 1-800-752-6007 OR LOCAL NO. 502-266-5123) FORTY EIGHT HOURS IN ADVANCE OF ANY CONSTRUCTION ON THIS PROJECT. THIS NUMBER WAS ESTABLISHED TO PROVIDE ACCURATE LOCATION SO EXISTING BELOW GROUND UTILITIES (I.E. CABLES, ELECTRIC WIRES, GAS AND WATERLINES). WHEN CONTRACTING THE "KENTUCKY 811" CALL CENTER, PLEASE STATE THAT THE WORK TO BE DONE IS FOR A PROPOSED MSD SEWER OR DRAINAGE FACILITY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR BECOMING FAMILIAR WITH ALL UTILITY REQUIREMENTS SET FORTH ON THE PLANS IN THE TECHNICAL SPECIFICATIONS AND SPECIAL PROVISIONS.

SANITARY SEWER NOTES


- 1. THE PROPOSED BUILDING WILL NOT HAVE ANY FACILITIES THAT REQUIRE A PSC CONNECTION
- 2. CONSTRUCTION PLANS AND DOCUMENTS SHALL COMPLY WITH LOUISVILLE AND JEFFERSON COUNTY METROPOLITAN SEWER DISTRICT'S DESIGN MANUAL AND STANDARD SPECIFICATIONS AND OTHER LOCAL, STATE, AND FEDERAL ORDINANCES.
- 3. SITE IS SUBJECT TO REGIONAL FACILITY FEE'S.
- 4. SITE DRAINAGE SHALL BE DIRECTED TO THE S. PRESTON STREET RIGHT-OF-WAY. KYTC APPROVAL REQUIRED PRIOR TO MSD CONSTRUCTION PLAN APPROVAL FOR THE INCREASE IN RUN OFF TO THE RIGHT-OF-WAY.
- 5. AN EPSC PLAN SHALL BE DEVELOPED AND APPROVED IN ACCORDANCE WITH MSD DESIGN MANUAL AND STANDARD SPECIFICATIONS PRIOR TO CONSTRUCTION PLAN APPROVAL.

GENERAL NOTES

- 1. NO PARKING AREAS ARE TO BE PROVIDED WITH THIS DEVELOPMENT. THE ONLY SITE IMPROVEMENT WILL BE THE ADDITION OF THE NEW BUILDING.
- 2. NO PORTION OF THE SITE IS WITHIN THE 100-YEAR FLOODPLAIN PER FIRM MAPS No. 21111C0041E & 21111C0042E, BOTH DATED DECEMBER 5TH, 2006.
- 3. NO DUMPSTERS/REFUSE CONTAINERS OR SERVICE STRUCTURES ARE TO BE PROVIDED WITH THIS DEVELOPMENT.
- 4. NO ADDITIONAL LIGHTING WILL BE PROVIDED WITH THIS DEVELOPMENT.
- 5. THERE ARE NO WETLANDS OR FLOODPLAIN RECORDED ON THIS PROPERTY.
- 6. PRIOR TO ANY CONSTRUCTION ACTIVITIES ON THE SITE. AN EROSION & SILT CONTROL PLAN SHALL BE PROVIDED TO MSD FOR APPROVAL.
- 7. NO ADDITIONAL WATER SERVICES WILL BE REQUIRED FOR THIS DEVELOPMENT.
- 8. CONSTRUCTION PLANS, BOND AND PERMIT ARE REQUIRED BY METRO PUBLIC WORKS PRIOR TO CONSTRUCTION APPROVAL.
- COMPATIBLE UTILITIES, IF NEEDED, SHALL BE PLACED IN A COMMON TRENCH UNLESS OTHERWISE REQUIRED BY APPROPRIATE AGENCIES.
- 10. MATERIALS STORED WITHIN THE PROPOSED BUILDING SHALL BE MOVED BY HAND, AND THEREFORE WILL NOT REQUIRE ANY TRUCK MANEUVERING ON THE SITE.
- 11. IF, DURING CONSTRUCTION, EXISTING SIDEWALKS ARE DAMAGED. RECONSTRUCTION AND REPAIRS SHALL BE REQUIRED, AS NECESSARY, TO MEET CURRENT METRO PUBLIC WORKS STANDARDS AND SHALL BE INSPECTED PRIOR TO FINAL BOND RELEASE.
- 12. A RECIPROCAL ACCESS AND CROSSOVER AGREEMENT SHALL BE CREATED AND RECORDED BETWEEN THE ADJOINING PROPERTY OWNERS TO THE EAST.
- 13. MITIGATION MEASURES FOR DUST CONTROL SHALL BE IN PLACE DURING CONSTRUCTION TO PREVENT FUGITIVE PARTICULATE EMISSIONS FROM REACHING EXISTING ROADS AND NEIGHBORING PROPERTIES. 14. CONTACT SHALL BE MADE WITH METRO EMERGENCY
- SERVICES PRIOR TO THE CONSTRUCTION PERMITTING PROCESS TO ESTABLISH AN ADDRESS FOR THE PROPOSED STRUCTURE.
- 15. CONSTRUCTION WORK SHALL NEITHER IMPACT NOR BE PERMITTED IN THE KYTC STATE RIGHT-OF-WAY.



NOTE: THIS DRAWING IS INTENDED TO BE PLOTTED IN COLOR. IF THIS SHEET APPEARS IN BLACK AND WHITE, IT IS PLOTTED INCORRECTLY. DISCARD AND OBTAIN AN ACCURATE DRAWING.



EX. GARAGE

± 720 SF

Ex. Building

LEGEND

PROPERTY LINE

EXISTING CHAIN

EX. / PROP. FORM

DISTRICT LINE

DISTRICT LINE

PROPOSED

PROPOSED

REMOVED FORM

DECIDUOUS TREE

PRIVACY FENCE

-0-0-0-0

LINK FENCE

EX. WOODEN

FENCE

100' TRANSITION ZONE

EX. FENCE IN R/W TO 4

BE REMOVED


Ex. Grass

Ex. Grass

Ex. Gravel

EX. BUILDING

± 2,352 SF



ADJACENT PROPERTY INFO (2nd Tier)

PARCEL ADDRESS: 1356 S. Preston Street



NOT TO SCALE

SITE DATA PROJECT DATA SITE AREA

39,712 SF (± 0.91 Ac.) DISTURBED AREA 5,000 SF **NET INCREASE OF IMPERVIOUS SURFACE** 4,080 SF EXISTING FORM DISTRICT TRADITIONAL NEIGHBORHOOD PROPOSED FORM DISTRICT TRADITIONAL WORKPLACE **EXISTING ZONING** C2 & OR2 PROPOSED ZONING EXISTING USE VACANT BUILDINGS (TO REMAIN)/LOT PROPOSED USE OPEN STORAGE BUILDING

BUILDING INFORMATION PROPOSED BUILDING (PIPE STORAGE) 4,080 SF EXISTING VACANT BUILDING (TO REMAIN) 2,352 SF EXISTING GARAGE (TO REMAIN) 718 SF TOTAL BUILDING AREA 7,150 SF MAXIMUM FLOOR AREA RATIO (F.A.R.) ALLOWED . 5.0 PROPOSED F.A.R. 0.18 MAXIMUM BUILDING HEIGHT ALLOWED 45'-0" PROPOSED BUILDING HEIGHT 18'-0" SITE DIMENSIONAL REQUIREMENTS (EZ1) MINIMUM FRONT YARD / STREET SIDE YARD SETBACK 0 FT¹

SIDE YARD SETBACK REAR YARD SETBACK 1. PER TABLE 5.2.2: MIXED USE AND NON-RESIDENTIAL STRUCTURES ON CORNER LOTS MAY HAVE A ZERO FRONT YARD & STREET SIDE YARD SETBACK/BUILD-TO LINES IN THESE ZONING DISTRICTS 2. SEE VARIANCE REQUEST

MAXIMUM FRONT YARD / STREET SIDE YARD SETBACK

PARKING REQUIREMENTS PROPOSED USE STORAGE UNIT OF CALCULATION **EMPLOYEES** NO. OF EMPLOYEES MIN. REQUIRED PARKING 1 SPACE PER 1.5 EMPLOYEES MAX. REQUIRED PARKING 1 SPACE PER EMPLOYEE TOTAL REQUIRED

TREE CANOPY REQUIREMENTS (CLASS A) TOTAL SITE AREA 39,712 SF N/A (NO EXISTING TREES) TREE CANOPY TO BE PRESERVED **NEW TREE CANOPY REQUIRED** 10% TREE CANOPY TO BE PLANTED (6 TYPE "A" TREES @ 720 SF) 4,320 SF TOTAL TREE CANOPY PROVIDED 4,320 SF, OR 11%

VARIANCE REQUESTS

- 1. A VARIANCE IS REQUESTED TO REDUCE THE REQUIRED 20'-0" REAR YARD SETBACK (LDC 5.2.5.C.3.c) BY 13'-0", THUS RESULTING IN A 7'-0" REAR YARD SETBACK.
- 2. A VARIANCE IS REQUESTED TO ALLOW THE PROPOSED STORAGE STRUCTURE TO BE PLACED FURTHER THAN 5'-0" AWAY FROM THE RIGHT-OF-WAY LINE OF BOTH S. JACKSON STREET AND S. PRESTON STREET (LDC 5.5.1.A.2).

WAIVER REQUESTS

- 1. A WAIVER IS REQUESTED TO NOT PROVIDE THE SCREENING REQUIRED BETWEEN THE ACCESSORY STRUCTURE AND SOUTH PRESTON STREET (LDC 5.5.5.A.1).
- 2. A WAIVER IS REQUESTED TO NOT PROVIDE THE LANDSCAPE BUFFER AND ASSOCIATED PLANT MATERIAL ALONG THE NORTH PROPERTY LINE THAT IS ADJACENT TO OR-2 ZONING (LDC 10.2.4).

AMENDMENT REQUEST

Midwest Sprinkler Corp.

1420 S. Jackson Street

Louisville, KY 40208

IT IS REQUESTED THAT THE PLANNING COMMISSION AMEND THE RESTRICTION SET FORTH IN LDC 2.6.1.A.1, WHICH REQUIRES A 200'-0" SETBACK FROM ANY RESIDENTIAL USE ADJACENT TO THE PROPERTY.

Site Development Plan full size plot scale: 1"=20'-0" OWNER/DEVELOPER OWNER SOURCE OF TITLE SITE ADDRESS

DB 10781 / PG 519

(Parcels 023 F001 00000)

Sprinkler S B O Midw O **DESIGN SERVICES**

S

in

P

.<u>P</u>

 $\mathbf{\Omega}$

© 2014 KovertHawkins Architects

- 7 m 4 m 0

CONDITIONS:

RELIMINARY APPROVAL

25 FT

10 FT²

0

WM# 11800

1375 S. Preston St.

Louisville, KY 40208

1820NE1080