
10-31-19 FOR CONSTRUCTION

SITE PLAN & INDEX

RECEIVED

PLANNING &



COPYRIGHT NOTICE

(C) GARY WATROUS 2019

DRAWING INDEX

AX1 - Site Plan & Notes & Index AX1.1 - Foundation Plan A

AX2 - Main Level Floor Plan

AX3 - Lower Level Plan AX4 - Main Level Floor Framing, Roof Plan

AX5 - Building Sections A,B,C

& Roof Framing

- Building Sections E,F,G

- Ext. Elevations: South & East

- Ext. Elevations: North & West

- Wall Sections & Details

AX10 - Wall Sections & Details

AX11 - Wall Structure Diagrams

NOTES TO CONTRACTORS

- 1. This job will be "Cost Plus A Fixed Percentage Fee" bid. Use bid forms provided by Architect
- 2. Allowances: Provide for following allowance items (mtl = material only, inst=installed price):

a. Windows (mtl): . b. Ext. Doors (mtl): c. Garage Doors & Openers (mtl): . d. HVAC & Fresh Air Systems (inst): . . e. Light Fixtures (mtl): = \$ 3,000 f. Finish Flooring (inst): = \$ 20,000 g. Cab. & Counter (inst): = \$ 15,000 i. Metal Railing (inst): . . k. Conc. Ret. Walls (inst): = \$ 25,000

3. Scope Of Work: Provide a complete and fully operational home. Kitchen appliances Not Included In Contract (NIC)

I. Segmented Retaining Wall (inst): . . = \$15,000

4. <u>Code</u>: All work must comply with all applicable provisions and requirements of all buildings and zoning codes for this site location.

5. Permits: Each Contractor or subcontractor shall make required application for and obtain all necessary permits, pay all fees (including tap fees) and obtain all necessary certificates and approvals for this work.

6. Checking: Each Contractor is responsible for checking all conditions and dimensions before proceeding with any portion of his work. Any discrepancies are to be reported to the Architect prior to proceeding. Failure to do shall make the Contractor subject to a correction method as may be later called for by the Architect. Each Contractor shall coordinate his work with the work of all other contractors. Contractor to verify all openings and chases for stairs, flues and ductwork, etc. in relation to framing shown to ensure proper fit and clearances of these items prior to starting framing work.

7. Workmanship: All labor is to be performed in the workmanlike manner by skilled mechanics only. Contractor to provide a complete and operating installation including all obvious and necessary items even though such items are not indicated on the drawings. It is assumed that when a subcontractor starts his work he accepts the substrate below unless written objection is made. All items are to be installed per manufacturer's written recommendations. Owner and Architect to approve all finish materials prior to

8. Clean Up: Each Contractor shall be responsible to clean up his work area daily and remove debris, droppings, and spillage, and shall repair all damage caused by him.

9. Insurance: The Contractor shall maintain such insurance as will protect him from claims under workmen's compensation and from any other claims for damages for personal injury, including death and property damage, which may arise from operations under this contract, whether such operations be by himself or by any subcontractor or anyone directly or indirectly employed by either of them. Copy of certificate of such insurance shall be attached to bid documents submitted by the contractor. Contractor shall provide insurance so that Owner and Architect shall be blameless in case of any accident or injury. The Contractor shall maintain insurance against theft or vandalism of building or building materials in the amount necessary to protect himself and the Owner.

10. Harmless: Contractor shall save the Architect and Owner, their associates and agents, harmless from any action brought against them as a result of changes made without written permission from the Architect, even though known to the Architect or Owner.

11. How to Bid Electric: provide 200 amp service.

a) outlets: bid per code b) switches: bid 3 per room av. c) Lighting Fixt: all fixtures to be surface mtd.; bid 4 av. per room. One fixture & switch per closet. Three garage door openers. 12 exterior lights mtd on house. d) Fans: provide exhaust fan & switch at Bathrooms. Provide a range hood vented thru exterior wall with switch. House will have all electric appliances (except gas range) purchased by Owner and installed by Contractor. All ceiling lighting will be surface mounted.

12. How to Bid Plumbing: Provide PEX piping. Provide PVC waste below slab. Toilet fixtures and hardware purchased by Owner, installed by Contractor.

13. How to Bid HVAC System: see HVAC allowance (a Duel Fuel Heat Pump System with fresh air system for House and PETK Unit for AirBB will be specified). HVAC contractor to do Manual J calculations and provide HVAC drawings in consultation with the Architect. All ductwork to be metal mastic sealed joint, insulated and secured to structure. Vertical return air duct runs inside interior walls.

THIS IS A REISSUED DRAWING WITH REISSUE DATE SHOWN ABOVE. A CHANGE WILL ONLY BE INDICATED WITH A CLOUD IF IT SIGNIFICANTLY IMPACTS JOB PRICE.