DEVELOPMENT NOTES


- . EXISTING SITE AND BOUNDARY INFORMATION SHOWN HEREON, PROVIDED TO AL ENGINEERING INC. BY QK4. BOUNDARY INFORMATION WAS REFERENCED TO THE MINOR PLAT ON FILE AT THE COUNTY CLERKS OFFICE (19MINORPLAT1079).
- 2. SUBJECT PROPERTY IS LOCATED WITHIN THE CITY OF LOUISVILLE.
- 3. ELECTRIC SERVICE TO BE COORDINATED WITH LOUISVILLE GAS AND ELECTRIC.
- 4. WATER SERVICE TO BE COORDINATED WITH THE LOUISVILLE WATER COMPANY.
- 5. PROPERTY IS IN PLEASURE RIDGE PARK FIRE DISTRICT AND SUBJECT TO APPROVAL.
- 6. ALL LUMINAIRES SHALL BE AIMED, DIRECTED, OR FOCUSED SUCH AS TO NOT CAUSE DIRECT LIGHT FROM THE LUMINAIRE TO BE DIRECTED TOWARD RESIDENTIAL USES OR PROTECTED OPEN SPACES ON ADJACENT OR NEARBY PARCELS, OR TO CREATE GLARE PERCEPTIBLE TO PERSONS OPERATING MOTOR VEHICLES ON PUBLIC STREETS AND
- 7. MITIGATION MEASURES FOR DUST CONTROL SHALL BE IN PLACE DURING CONSTRUCTION TO PREVENT FUGITIVE PARTICULATE EMISSIONS FROM REACHING EXISTING ROADS AND NEIGHBORING PROPERTIES.
- 8. "NO IDLING" SIGNS SHALL BE POSTED AT ALL LOADING/UNLOADING DOCK AREAS.
- 9. THE EXISTING UTILITIES SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL CONTACT "BUD" TOLL FREE 1-800-752-6007 FOR LOCATION OF UNDERGROUND UTILITIES BEFORE EXCAVATION BEGINS.
- 10. A PORTION OF THE PROPERTY LIES WITHIN A FLOOD HAZARD AREA PER FEMA FIRM PANEL 21111C01136E, DATED 12/05/2006.
- 11. CAMPATABLE UTILITIES SHALL BE PLACE IN A COMMON TRENCH UNLESS OTHERWISE REQUIRED BY APPROPRIATE AGENCIES.
- 12. ALL SERVICE STRUCTURES SHALL BE SCREENED IN ACCORDANCE WITH LAND DEVELOPMENT CODE CHAPTER 10, SECTION 10.2.6 AND 10.4.9.
- 13. A KARST SURVEY WAS CONDUCTED ON THIS SITE ON FEBRUARY 26, 2020 BY SANDOR R. GREENBAUM P.E. OF GREENBAUM ASSOCIATES. INC.
- 14. ALL SIGNAGE WILL WILL COMPLY WITH LDC CHAPTER 8 REQUIREMENTS AND ANY APPLICABLE PERMITTING.
- 15. PER LDC 9.1.12.C CURBING AT LEAST SIX (6) INCHES HIGH AND SIX (6) INCHES WIDE SHALL BE PROVIDED TO PREVENT VEHICLES FROM OVERHANGING ABUTTING SIDEWALKS, PROPERTIES OR PUBLIC RIGHTS—OF—WAY, TO PROTECT LANDSCAPED AREAS AND TO PROTECT ADJACENT PROPERTIES.
- 16. MOSQUITO CONTROL IN ACCORDANCE WITH CHAPER 96 OF LOUISVILLE JEFFERSON COUNTY METRO ORDINANCES.
- 17. THIS PLAN MUST COMPLY WITH ALL CURRENT METRO SMOKING ORDINANCES.

PUBLIC WORKS NOTES

- 1. FORTY EIGHT (48) HOURS PRIOR TO CONSTRUCTION, NOTICE SHALL BE GIVEN BY THE CONTRACTOR TO LOUISVILLE METRO PUBLIC WORKS DEPARTMENT FOR INSPECTIONS OF BASE, PAVEMENT AND SIDEWALKS.
- 2. ALL CONSTRUCTION METHODS, MATERIALS AND WORK ACTIVITIES SHALL BE IN ACCORDANCE WITH THE KENTUCKY TRANSPORTATION CABINET DEPARTMENT OF HIGHWAYS STANDARD SPECIFICATIONS AND SUPPLEMENT FOR ROAD AND BRIDGE CONSTRUCTION LATEST EDITION UNLESS OTHERWISE SPECIFIED. THE CURRENT KENTUCKY STANDARD DRAWINGS WILL ALSO APPLY UNLESS OTHERWISE NOTED ON THE PLANS.
- CONSTRUCTION PLANS, BOND AND ENCROACHMENT PERMIT IS REQUIRED BY LOUISVILLE METRO PUBLIC WORKS DEPARTMENT, FOR ANY WORK IN PUBLIC RIGHT OF WAYS.
- 4. ALL SIDEWALK RAMPS SHALL CONFORM TO A.D.A. STANDARD SPECIFICATIONS, THE "SPECIAL NOTE FOR DETECTIBLE WARNINGS FOR RAMPS" PER KTC STANDARD DRAWINGS FOR SIDEWALKS AND PER "KY STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" LATEST EDITION.
- 5. ALL SIDEWALKS, PEDESTRIAN RAMPS, LANDINGS, AND CROSSWALKS, ALONG THE ACCESSIBLE ROUTE SHALL CONFORM TO THE AMERICAN DISABILITIES ACT (A.D.A.).
- 6. ALL TRAFFIC SIGNS AND STRIPING SHALL BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) FOR STREETS AND HIGHWAYS, CURRENT EDITION.


MSD NOTES

- 1. CONSTRUCTION PLANS AND DOCUMENTS SHALL COMPLY WITH LOUISVILLE AND JEFFERSON COUNTY METROPOLITAN SEWER DISTRICT'S DESIGN MANUAL AND STANDARD SPECIFICATIONS.
- 2. SANITARY SEWER SERVICE PROVIDED BY RIVERPORT AUTHORITY LATERAL EXTENSION 1102629. SANITARY SEWER CAPACITY FEES MAY APPLY.
- 3. EXISTING PONDING AND FLOWAGE EASEMENTS WERE RELEASED BY DEED BOOK 11487 PAGE 405.
- 4. THE PORTION OF THE SITE WITHIN THE 100 YEAR FLOODPLAIN HAS BEEN APPROVED FOR PLACEMENT OF FILL. FLOODPLAIN COMPENSATION (1.5:1) IS PROVIDED OFF SITE ON LOT 4, RIVERPORT PHASE 5.
- DIVISION OF WATER AND U.S. ARMY CORP OF ENGINEERS PERMITTING (INCLUDING WETLANDS) WAS APPLIED FOR BY RIVERPORT AUTHORITY AND HAS BEEN APPROVED.
- 6. THE INCREASE IN RUNOFF HAS BEEN COMPENSATED FOR BY RIVERPORT AUTHORITY ON LOT 4, PHASE 5 "FLOODPLAIN COMPENSATION/RUNOFF AREA"
- 7. MS4 WATER QUALITY REGULATIONS FOR THIS SITE ARE BEING PROVIDED BY RIVERPORT AUTHORITY BY INSTALLTION OF WATER QUALITY UNIT ON LOT 4.



TYPICAL PARKING LAYOUT

100




- 100.00 -

Proposed Manhole

Existing Contour

— 100.00 — Proposed Contour



INC

ENGINEERING

H

8 8 Z

4BEL Construction 2401 Stanley Gault Parkw. Louisville. Kv. 40223

INC.

T PLAN

REVISED DETA

DRAWING

VICINITY MAP

Site Development Data

NO SCALE

Location:
Inst. No.
Inst. No.
Tax Block, Lot, Sublot:
Area:

Zoning:
Form District:
Enterprise Zone:
Existing Use:
Plan Certain:

6650 RANDY COE LANE
D.B. 11488 PG. 767
1059-0040-0000
40.0 Acres
1,742,400 S.F.
EZ1
SW
ENCENTED VACANT
OFFICE/WAREHOUSE
13ZONE1021

OWNER
NAME
PACCAR INC.
ADDRESS
777 106TH AVE. N.E.
CITY, STATE, ZIP
BELLEVUE, WA. 98004

Building Summary

Warehouse: 10,715 S.F. 258,993 S.F.

Total Building Area: 269,708 S.F.

F.A.R. 0.155
Max Allowed F.A.R. 5
Building Height: 45'

Phase Il South Expansion: 128,250 S.F. Phase Il East Expansion: 293,670 S.F.

Dimensional Standards

Building Setbacks Min Perimeter Bufferi Front: 25' 15' LBA Side: NONE 15' LBA Street Side: 25' 15' LBA Rear: NONE 15' LBA Railroad: 35' Max. Height of Building: 50'

Parking Summary

 Office
 Min 1SP/350S.F. 10,715 31
 Max 1SP/200S.F. S.F. 54

 Warehouse
 1SP/1.5EMP 73 49
 1SP/1.0EMP Employees 73

 Total Spaces Required
 80
 127

 Spaces Provided
 111 5 116
 spaces ADA spaces Total

 Bicycle Parking
 2 Long-Term
 2 Short-Term

I L A Requirements

Loading & Storage Area: 135,808 S.F.
Vehicle Use Area: 46,923 S.F.
ILA Required: (7.5%) 3,519 S.F.
ILA Provided: (13.5%) 6,136 S.F.
ILA Trees Required:(1/4000 S.F.) 12 trees
ILA Trees Provided: 14 trees

Impervious Areas

Total Site Area 1,742,400 S.F.
Existing Conditions
Impervious 0 S.F.
Pervious 1,742,400 S.F.
Proposed Conditions
Impervious 464,460 S.F.
Pervious 1,277,940 S.F.

RECEIVED
SEP 04 2020

PLANNING & DESIGN SERVICES

AMENITY AREA

Required Area 10% Office 1,072 S.F.
Provided Area 1072.5 S.F.
Required Seating 1 seat/200 SF 6.0 seats
Provided Seating 12 seats

Tree Canopy

20724-REV EXT.5

LRL-2012-737-mck

USACE:

Class C Tree Canopy Category
Gross Site Area
Existing Tree Canopy
Ex. Tree Canopy %

New Tree Canopy Required %

New Tree Canopy Area Required

1,742,400 S.F 0 S.F 0.0 % 20.0 % 348,480 S.F

1FP - MM9