

- CONSTRUCTION PLANS AND DOCUMENTS SHALL COMPLY WITH LOUISVILLE AND JEFFERSON COUNTY METROPOLITAN SEWER DISTRICT'S DESIGN
- 2. DRAINAGE PATTERN DEPICTED BY ARROWS IS FOR CONCEPT PURPOSES ONLY. FINAL CONFIGURATION AND DESIGN OF DRAINAGE PIPES AND CHANNELS SHALL BE DETERMINED DURING THE CONSTRUCTION PLAN DESIGN PROCESS. DRAINAGE FACILITIES SHALL CONFORM TO
- 3. AN APPROVED EROSION PREVENTION AND SEDIMENT CONTROL (EPSC) PLAN SHALL BE IMPLEMENTED PRIOR TO ANY LAND DISTURBING ACTIVITY ON THE CONSTRUCTION SITE. ANY MODIFICATION TO THE APPROVED EPSC PLAN MUST BE REVIEWED AND APPROVED BY MSD'S PRIVATE DEVELOPMENT REVIEW OFFICE. EPSC BMP'S SHALL BE INSTALLED PRE THE PLAN AND MSD STANDARDS.
- 4. DETENTION BASINS, IF APPLICABLE, SHALL BE CONSTRUCTED FIRST AND SHALL PERFORM AS SEDIMENT BASINS DURING CONSTRUCTION UNTIL THE CONTRIBUTING DRAINAGE AREAS ARE SEEDED AND STABILIZED.
- 5. ACTIONS MUST BE TAKEN TO MINIMIZE THE TRACKING OF MUD AND SOIL FROM CONSTRUCTION AREAS ONTO PUBLIC ROADWAYS. SOIL TRACKED ONTO THE ROADWAY SHALL BE REMOVED DAILY.
- 6. SOIL STOCKPILES SHALL BE LOCATED AWAY FROM STREAMS, PONDS, SWALES AND CATCH BASINS. STOCKPILES SHALL BE SEEDED, MULCHED, AND ADEQUATELY CONTAINED THROUGH THE USE OF SILT FENCE.
- WHERE CONSTRUCTION OR LAND DISTURBANCE ACTIVITY WILL OR HAS TEMPORARILY CEASED ON ANY PORTION OF THE SITE, TEMPORARY SITE STABILIZATION MEASURES SHALL BE REQUIRED AS SOON AS PRACTICAL, BUT NO LATER THAN 14 CALENDAR DAYS AFTER THE
- 8. KYTC APPROVAL REQUIRED PRIOR TO MSD CONSTRUCTION PLAN APPROVAL.
- 9. SANITARY SEWER SERVICE PROVIDED BY PSC, SUBJECT TO FEES AND ANY APPLICABLE CHARGES.
- 10. MSD DRAINAGE BOND REQUIRED PRIOR TO CONSTRUCTION PLAN APPROVAL.
- 11. RUN-OFF VOLUME IMPACT FEE REQUIRED, CALCULATION BASED ON RFF x 1.5.
- 12. ONSITE DETENTION WILL BE PROVIDED. POST-DEVELOPED PEAK FLOWS WILL BE LIMITED TO PRE-DEVELOPED PEAK FLOWS FOR THE 2, 10, 25 AND 100-YEAR STORMS OR TO THE CAPACITY OF THE DOWNSTREAM SYSTEM, WHICHEVER IS MORE RESTRICTIVE.
- 13. UNDERGROUND DETENTION BASINS MUST MEET THE REQUIREMENTS OF SECTION 10.3.8.4 OF MSD'S DESIGN MANUAL.

GENERAL NOTES

- 1. THERE SHALL BE NO INCREASE IN DRAINAGE RUN-OFF TO THE RIGHT-OF-WAY.
- 2. THERE SHALL BE NO COMMERCIAL SIGNS IN THE RIGHT-OF-WAY.
- 3. THERE SHALL BE NO LANDSCAPING IN THE RIGHT-OF-WAY WITHOUT AN ENCROACHMENT PERMIT. TREE SPECIES PLANTED IN THE RIGHT-OF-WAY MUST CONFORM WITH DISTRICT 5 LIST OF APPROVED TREES.
- 4. CONSTRUCTION PLANS, ENCROACHMENT PERMIT AND BOND WILL BE REQUIRED BY KYTC AND METRO PUBLIC WORKS FOR ALL WORK DONE WITHIN STREET RIGHT-OF-WAY.
- 5. NO INCREASE IN VELOCITY AT POINT OF DISCHARGE AT PROPERTY LINE.
- 6. VERGE AREAS WITHIN PUBLIC RIGHT-OF-WAY TO BE PROVIDED PER METRO PUBLIC WORKS.
- 7. COMPATIBLE UTILITY LINES (ELECTRIC, TELEPHONE, CABLE) SHALL BE PLACED IN A COMMON TRENCH UNLESS OTHERWISE REQUIRED BY
- 8. MITIGATION MEASURES FOR DUST CONTROL SHALL BE IN PLACE DURING DEMOLITION AND CONSTRUCTION ACTIVITIES TO PREVENT FUGITIVE
- 9. BOUNDARY AND TOPOGRAPHIC INFORMATION TAKEN FROM SURVEY BY BTM ENGINEERING, INC.
- 10. DUMPSTERS AND SERVICE STRUCTURES TO BE SCREENED PER CHAPTER 10 REQUIREMENTS
- 11. BUILDING DESIGN WILL FOLLOW CHAPTER 5.5 AND 5.6 OF THE L.D.C.
- 12. EXISTING SIDEWALK RECONSTRUCTION AND REPAIRS SHALL BE REQUIRED, AS NECESSARY, TO MEET CURRENT METRO PUBLIC WORKS
- 13. SITE LIGHTING SHALL NOT SHINE IN THE EYES OF DRIVERS. IF IT DOES, IT SHOULD BE RE-AIMED, SHIELDED OR TURNED OFF.
- 14. ALL NEW OR EXISTING SIDEWALKS SHALL BE EITHER BROUGHT UP TO OR BUILT TO A.D.A. CURRENT STANDARDS.
- 15. ALL DRAINAGE STRUCTURES WITHIN STATE RIGHT-OF-WAY SHALL BE STATE DESIGN.
- 16. MOSQUITO CONTROL IN ACCORDANCE WITH CHAPTER 96 OF THE LOUISVILLE/JEFFERSON COUNTY METRO ORDINANCES.
- 17. STREET TREES SHALL BE PROVIDED PER CHAPTER 10 AND COMPLY WITH ALL METRO WORKS STANDARDS.
- 18. ALL SITE SIGNAGE SHALL COMPLY WITH CHAPTER 8 REQUIREMENTS OF THE LAND DEVELOPMENT CODE.
- 19. WHEEL STOPS OR CURBING AT LEAST 6" TALL SHALL BE PROVIDED TO PREVENT VEHICLES FROM OVERHANGING ABUTTING SIDEWALKS. PROPERTIES OR PUBLIC RIGHTS-OF-WAY, TO PROTECT LANDSCAPED AREAS AND TO PROTECT ADJACENT PROPERTIES. WHEEL STOPS SHOULD BE LOCATED 3' FROM ANY ADJACENT WALL, FENCE, PROPERTY LINE, WOODY VEGETATION, WALKWAY OR STRUCTURE.
- 20. UPON DEVELOPMENT OR REDEVELOPMENT OF ADJACENT PROPERTIES, A UNIFIED ACCESS AND CIRCULATION SYSTEM SHALL BE DEVELOPED TO ELIMINATE PRE-EXISTING CURB CUTS AND PROVIDE FOR VEHICULAR MOVEMENT THROUGHOUT ADJACENT SITES AS DETERMINED APPROPRIATE BY THE DEPARTMENT OF PUBLIC WORKS. A CROSS ACCESS AGREEMENT TO RUN WITH THE LAND AND IN A FORM ACCEPTABLE TO PLANNING COMMISSION LEGAL COUNSEL SHALL BE RECORDED PRIOR TO THE TIME OF CONSTRUCTION APPROVAL FOR THE ADJACENT PROPERTY TO BE DEVELOPED.
- 21. TARC ROUTE 43 IS LOCATED ALONG POPLAR LEVEL ROAD.
- 22. KENTUCKY TRANSPORTATION CABINET APPROVAL REQUIRED.
- 23. CALCULATIONS WILL BE REQUIRED FOR ANY RUNOFF DEEMED NECESSARY TO BE TAKEN TO THE STATE RIGHT-OF-WAY. PROPOSALS TO ALTER OR SIGNIFICANTLY INCREASE A DRAINAGE AREA OR RUNOFF FACTORS OR TO CHANGE IN ANY WAY THE PERFORMANCE OF AN EXISTING DRAINAGE STRUCTURE SHALL BE ACCOMPANIED BY A COMPLETE DRAINAGE SURVEY AND HYDROLOGIC ANALYSIS (UPSTREAM AND DOWNSTREAM) BASED ON 25-YEAR AND 100-YEAR STORMS. THIS ANALYSIS SHALL INCLUDE A COMPARISON OF EXISTING AND PROPOSED CONDITIONS. REQUEST TO ALTER DRAINAGE ON A RIGHT-OF-WAY SHALL RESULT IN CONDITIONS THAT ARE EQUAL TO OR BETTER THAN
- 24. DUMPSTER SERVICE PROVIDER WILL BE GRANTED ACCESS DURING NORMAL BUSINESS HOURS.
- 25. ADDRESSING SCHEME WILL BE DEVELOPED IN COORDINATION WITH LOUISVILLE METRO EMERGENCY SERVICES PRIOR TO REQUEST FOR

TREE CANOPY CALCULATIONS

TREE CANOPY CATEGORY CLASS C

SITE AREA	40,691	
EX. TREE CANOPY ON SITE	•	S.F. (15.5%)
3-36" OAKS "TYPE A" TREES @ 2,100 SF EA	6,300 SF	
EX. TREE CANOPY TO BE PRESERVED	0	S.F. (0%)
TREE CANOPY REQUIRED	14,242	S.F. (35%)
ADDITIONAL TREE CANOPY REQUIRED	14,242	S.F. (35%)
TREE CANOPY TO BE PROVIDED	14,400	S.F. (35.4%)
20 "TYPE A" TREES @ 720 SQ.FT.		
TOTAL TREE CANOPY TO BE PROVIDED	14,400	S.F. (35.4%)

APPROXIMATE DETENTION CALCULATION:


(5,227 CU-FT)

POST-DEVELOPED
PERVIOUS AREA
0.26 X 0.20 = 0.06
0.93 PRE-DEVELOPED PERVIOUS AREA $\begin{array}{c} 0.93 \times 0.20 = 0.20 \\ \hline 0.93 \end{array}$ IMPERVIOUS AREA IMPERVIOUS AREA $0.0 \times 0.95 = 0.00$ $0.67 \times 0.95 = 0.68$ PRE-DEVELOPED C = 0.20POST-DEVELOPED C = 0.74REQUIRED VOLUME: $(0.74-0.20) \times 2.9/12 \times 0.93 = 0.12 \text{ AC-FT}$

APPROXIMATE PROVIDED VOLUME: 6,588 CU-FT

IMPERVIOUS AREA (SITE) NET SITE AREA ----- 0.93 ACRES AREA OF DISTURBANCE ---- 0.83 ACRES EXISTING IMPERVIOUS SURFACE ---- 0.00 ACRES PROPOSED IMPERVIOUS SURFACE --- 0.62 ACRES (67%)

INCREASE IN IMPERVIOUS SURFACE --- 0.62 ACRES



CASE # 21-ZONE-0058 RELATED CASE # 20-ZONEPA-0106 MSD WM #12215

LOCATION MAP

NOT TO SCALE

SITE DATA

PARKING REQUIREMENT

TOTAL SITE AREA 0.93 ACRES (40,690.55 SQ.FT.) EXISTING ZONING R-4 EXISTING FORM DISTRICT NFD **VACANT** EXISTING USE PROPOSED ZONING PROPOSED USE OFFICE/CONTRACTOR SHOPS

PROPOSED BUILDING AREA 9,715 SQ.FT. OFFICE 2,680 SQ.FT. CONTRACTOR UNITS (9 w/18 EMP.) 7,035 SQ.FT.

FLOOR AREA RATIO 0.24

MINIMUM PARKING REQUIRED 11 SPACES OFFICE (2,680 SQ.FT.) 7 SPACES (1 SP/400 S.F.) 4 SPACES CONTRACTOR UNITS (1 SP/2000 SQ.FT.) MAXIMUM PARKING ALLOWED 27 SPACES

OFFICE (2,680 SQ.FT.) 13 SPACES CONTRACTOR UNITS 14 SPACES (1 SP/500 S.F.) PROP. PÁRKING PROVIDED 19 SPACES

<u>BICYCLE PARKING REQUIREMENTS</u> SHORT TERM SPACES 2 SPACES LONG TERM SPACES* 2 SPACES

*LONG TERM SPACES PROVIDED WITHIN BUILDING.


LANDSCAPE REQUIREMENTS

(INC. 2 ACCESSIBLE SPACES)

VEHICLE USE AREA 15,270 SQ.FT. 7.5% I.L.A. REQUIREMENT 1,145 SQ.FT. PROP. I.L.A. PROVIDED 1,392 SQ.FT.

VARIANCE AND WAIVER REQUESTS:

- 1. REQUEST VARIANCE OF CHAPTER 5.3.2 TO REDUCE THE WEST SIDE YARD (NON-RESIDENTIAL TO RESIDENTIAL WITH NO LOADING) SETBACK FROM 30' TO 10'.
- . REQUEST VARIANCE OF CHAPTER 5.3.2 TO REDUCE THE EAST SIDE YARD (NON-RESIDENTIAL TO RESIDENTIAL WITH LOADING) SETBACK FROM 50' TO 10'.
- 3. REQUEST WAIVER OF CHAPTER 10.2.4.A TO REDUCE THE REQUIRED LANDSCAPE BUFFER AREAS FROM 35' TO 10' ALONG THE SIDE YARDS.



DE CE DE: CHECKED BY: NOVEMBER 2, 2020 200206-DDP 1" = 20' 1.00

SIGNATURE

DATE

SIGNATURE

FOR